#### VPDES PERMIT FACT SHEET

This document gives the pertinent information concerning the reissuance of the VPDES permit listed below. This permit is being processed as a minor municipal permit. The effluent limitations contained in this permit will maintain the Water Quality Standards of 9 VAC 25-260-00 et seq.

The discharge results from the operation of a 0.20 MGD oxidation ditch treatment plant serving the Town of Pembroke. This permit action consists of decreasing the monitoring frequencies for BOD<sub>5</sub> and total suspended solids, revising the E. coli monitoring, revising the total residual chlorine limits (when applicable), and revising the special conditions. (SIC Code: 4952)

#### 1. Facility Name and Address:

Pembroke WWTP

PO Box 5

Pembroke, VA 24136

Location: 126 Park Lane, Pembroke

2. Permit No: VA0088048 Existing Permit Expiration Date: November 15, 2013

3. Facility/ Owner Contacts:

Mr. Stanley Lucas, Public Works Director, 540-626-7607; utilitydir@pemtel.net

Mr. Donald Poteet, Mayor, 540-626-7191

4. **Application Complete Date:** May 15, 2013

> Permit Drafted By: Becky L. France, Water Permit Writer

> > Date: July 9, 2013, Revised 8/13/13

DEO Regional Office: Blue Ridge Regional Office

Reviewed By: Kip D. Foster Water Permit Manager

Reviewer's Signature: Abel Viet Date:

Public Comment Period Dates: From 8/1/13 To

5. **Receiving Stream Classification:** 

> Receiving Stream: New River (River Mile: 50.82)

Watershed ID: VAW-N29R (New River Watershed)

River Basin: New River

River Subbasin: NA

> Section: 1

IV Class:

Special Standards: u

7-Day, 10-Year Low Flow: 486 MGD 7-Day, 10-Year High Flow: 836 MGD

1-Day, 10-Year Low Flow: 407 MGD 1-Day, 10-Year High Flow: 600 MGD 30-Day, 5-Year Low Flow: 708 MGD Harmonic Mean Flow: 1605 MGD

Tidal: No 303(d) Listed: Yes - PCBs

**Attachment A** contains a copy of the flow frequency determination memorandum.

- 6. Operator License Requirements: III
- 7. Reliability Class: II

8.	Permit	Characterization
· ·	T OF HILL	CHUI UCICI EUIOII

1 (1111	ni Characici	wation.	
()	Private	( )	Interim Limits in Other Document
( )	Federal	( )	Possible Interstate Effect
( )	State		
$(\mathbf{X})$	POTW		
( )	PVOTW		
( )	PVOIW		

9. Wastewater Treatment System: A description of the wastewater treatment system is provided below. See Attachment B for the wastewater treatment schematic and Attachment C for a copy of the site inspection report. Treatment units associated with the discharge are listed in the table below.

Table I
DISCHARGE DESCRIPTION

Outfall Number	Discharge Source	Treatment (Unit by Unit)	Flow (Design) (MGD)
001	Pembroke WWTP	bar screen comminutor grit chamber oxidation ditches (2) secondary clarifiers (2) UV disinfection banks (2) cascade aerator aerobic digesters sludge drying beds (4)	0.20

The Town of Pembroke operates a 0.20 MGD oxidation ditch system for the residents of the Pembroke area. The wastewater works consists of a bar screen, comminutor, grit chamber, oxidation ditches, clarifiers, UV light banks, cascade aerator, aerobic digesters, and sand drying beds. This facility began operation in 1996.

After flowing through a bar screen, comminutor, and grit chamber, the wastewater is routed through one of two aerated oxidation ditches. Then wastewater flows into two clarifiers. Solids that accumulate in a sludge hopper and the scum from the trough are wasted daily. The wastewater overflows the weirs and is disinfected by one of two banks of ultraviolet lights. Disinfected effluent flows through a cascade aerator and is discharged to the New River.

- 10. <u>Sewage Sludge Use or Disposal:</u> A VPDES Sewage Sludge Permit Application Form was submitted for this facility to address disposal of sewage sludge from the wastewater treatment facility. Sludge is aerobically digested and then dewatered in drying beds. Dewatered sludge is periodically hauled to the New River Resource Authority in Dublin, Virginia.
- 11. <u>Discharge Location Description:</u> A USGS topographic map which indicates the discharge location, any significant dischargers, any water intakes, and other items of interest is included in **Attachment D**. The latitude and longitude of the discharge are N 37<sup>0</sup>18 51.98", E 80<sup>0</sup>38 34.00".

Name of Topo: <u>Pearisburg</u> Number: <u>112C</u>

- 12. Material Storage: NA
- 13. <u>Ambient Water Quality Information:</u> Memoranda or other information which helped to develop permit conditions (special water quality studies, STORET data, and any other biological and/or chemical data, etc.) are listed below.

#### Receiving Stream Classification

Pembroke WWTP discharges into the New River Watershed (VAW-N24R). The Virginia Department of Health has issued a health advisory for a segment of the New River from the Route 114 bridge crossing just north of Radford downstream to the Virginia/West Virginia state line near Glen Lyn. This stream segment is impaired due to PCBs found in fish tissue.

#### Flow Frequency Data

Flow frequencies for outfall 001 were recalculated using flow frequencies for the gauges at Eggleston and Glen Lyn. The Eggleston gauge is located at the Route 730 bridge in Eggleston, Virginia 4 miles upstream of the discharge point. The nearest downstream continuous record gauge on the New River is located at Glen Lyn, Virginia. There are several discharges and withdrawals between the discharge point and the Glen Lyn gauge.

Since there is no current flow information for the Eggleston gauge, flow frequencies for the gauge were determined by calculating a ratio of Glen Lyn and Eggleston gauge data from the same period of record (1940 - 1976) and multiplying the ratio by the current flow frequencies at Glen Lyn. To solve for the flow frequencies at the discharge point, a ratio of the drainage area of the Eggleston gauge and the discharge point were used to calculate the flow at the discharge point. Attachment A contains a copy of the flow frequency determination memorandum.

#### Stream Water Quality Data

The nearest downstream STORET monitoring station (9-NEW030.15) is located at the Route 460 bridge in Glen Lyn, Virginia. This station is just below APCO's intake and the APCO-Glen Lyn discharge for outfalls 001, 002, and 003. The 90<sup>th</sup> percentile pH and average hardness used in the wasteload allocation spreadsheets were determined from STORET Station 9-NEW030.15 in Glen Lyn. Since the discharges from the APCO facility include noncontact cooling water, the temperature values at this station were not used to determine the 90<sup>th</sup> percentile temperature value. Metals and PCB data have also been collected for this monitoring station.

The nearest upstream STORET monitoring station (9-NEW056.22) is located at the Route 760 bridge in Eggleston, Virginia. This station is located above the Celanese Acetate plant in Narrows and cannot be used for background metals data. Since there are no non-contact cooling water discharges upstream of this station, the 90<sup>th</sup> percentile temperature used in the wasteload allocation was determined from this station. The monitoring data for these stations are included in **Attachment E**.

#### **Endangered Species Evaluation**

The Department of Conservation and Recreation's Division of Natural Heritage (DCR) has identified natural heritage resources in the project area. The Candy Darter and Hellbender have been historically documented in the New River.

#### 14. Antidegradation Review and Comments: Tier 1 Tier 2 X Tier 3

The State Water Control Board's Water Quality Standards includes an antidegradation policy (9 VAC 25-260-30). All state surface waters are provided one of three levels of antidegradation protection. For Tier 1 or existing use protection, existing uses of the water body and the water quality to protect these uses must be maintained. Tier 2 water bodies have water quality that is better than the water quality standards. Significant lowering of the water quality of Tier 2 waters is not allowed without an evaluation of the economic and social impacts. Tier 3 water bodies are exceptional waters and are so designated by regulatory amendment. The antidegradation policy prohibits new or expanded discharges into exceptional waters.

The antidegradation review begins with Tier determination. The New River is not listed as a public water supply in the segment where the discharge is located. The New River in this segment (VAW-N29R) is listed on Part I of the 303(d) list for PCBs in fish tissue. However, according to Agency guidance, fish tissue analysis and metals in sediments are not a basis for determining a receiving stream as Tier 1. Available pollutant data have been analyzed, and the existing water quality condition for pollutants for which data exist compared to the water quality standards. This analysis indicates the water quality of the receiving stream does not exceed numeric criteria for any pollutant analyzed. Therefore, this segment of the New River is classified as a Tier 2 water, and no significant degradation of existing quality is allowed.

For purposes of aquatic life protection in Tier 2 waters, "significant degradation" means that no more than 25 percent of the difference between the acute and chronic aquatic criteria values and the existing quality (unused assimilative capacity) may be allocated. For purposes of human health protection, "significant degradation" means that no more than 10 percent of the difference between the human health criteria and the existing quality (unused assimilative capacity) may be allocated. The antidegradation baselines for aquatic life and human health are calculated for each pollutant as follows:

Antidegradation baseline (aquatic life) = 0.25 (WQS - existing quality) + existing quality Antidegradation baseline (human health) = 0.10 (WQS - existing quality) + existing quality Where:

"WQS" = Numeric criterion listed in 9 VAC 25-260-00 et seq. for the parameter analyzed "Existing quality" = Concentration of the parameter being analyzed in the receiving stream

When applied, these "antidegradation baselines" become the new water quality criteria in Tier 2 waters, and effluent limits must be written to maintain the antidegradation baselines for each pollutant. Antidegradation baselines have been calculated as described above and included in **Attachment G**.

Since this discharge began in 1996 when construction of the Pembroke WWTP was completed, antidegradation guidelines are applicable and have been applied to this permit reissuance. Water quality based effluent limits for pH and total residual chlorine (TRC) have been established in compliance with antidegradation requirements set forth in 9 VAC 25-260-30 of the water quality standards regulations. In accordance with antidegradation policy, pH will be maintained within the range of 6.0 S.U. and 9.0 S.U. For BOD<sub>5</sub>, antidegradation has been applied to prevent a significant lowering of dissolved oxygen (DO) more than 0.20 mg/L from the existing level (90 percent DO saturation value) in the receiving stream. The antidegradation review was conducted as described in Guidance Memo 00-2011, and complies with the antidegradation policy contained in Virginia's Water Quality Standards. The permit limits are in compliance with antidegradation requirements set forth in 9 VAC 25-260-30.

- 15. <u>Site Inspection:</u> Date: <u>4/16/13</u> Performed by: <u>Becky L. France</u>

  Attachment C contains a copy of the site inspection memorandum. The last DEQ laboratory and technical inspection was conducted by Ryan L. Hendrix on April 10, 2013.
- 16. Effluent Screening and Limitation Development: DEQ Guidance Memo 00-2011 was used in developing all water quality based limits pursuant to water quality standards (9 VAC 25-260-5 et seq.). The 90<sup>th</sup> percentile stream temperatures were calculated from an upstream STORET monitoring station in Eggleston. The 90<sup>th</sup> percentile pH and average hardness values were calculated from a downstream STORET monitoring station in Glen Lyn. The effluent 90<sup>th</sup> temperature percentiles calculated from effluent data collected from July 2007 through June 2008 were carried forward from a previous permit cycle. The effluent 90<sup>th</sup> pH percentiles were calculated from effluent data collected during the permit term from January 2008 through August 2012. The effluent hardness data collected on April 4, 2007 during the previous permit term was used in the wasteload allocation spreadsheet calculations. Refer to Attachment E for stream data and Attachment F effluent data used in these calculations. Refer to Attachment G for the antidegradation wasteload allocation spreadsheet and effluent limit calculations. See Table II on page 16 for a summary of limitations and monitoring requirements and Table III on page 17 for a summary of changes to the limitations and monitoring requirements.

#### A. Mixing Zone

The Agency mixing zone program, MIXER, was run to determine the percentage of the receiving stream flow that can be used in the antidegradation wasteload allocation calculations. The program indicated that 0.66 percent of the 1Q10 and 37.43 percent of

the 7Q10 may be used for calculating the acute and chronic antidegradation wasteload allocations (AWLAs). A copy of the printout from the MIXER run is included in **Attachment G**.

#### B. Effluent Limitations for Conventional Pollutants

Flow -- The permitted design flow of 0.20 MGD for this facility is taken from the previous permit and the application for the reissuance. In accordance with the VPDES Permit Manual, flow is to be measured on a continuous basis with totalizing, indicating, and recording equipment.

pH – Between May 2010 and April 2013 there were no exceedances of the pH limitations. The pH limits of 6.0 S.U. minimum and 9.0 S.U. maximum have been continued from the previous permit. These limits are based upon the water quality criteria in 9 VAC 25-260-50 for Class IV receiving waters and are in accordance with federal technology-based guidelines, 40 CFR Part 133, for secondary treatment. Grab samples shall continue to be collected once per day.

**Total Suspended Solids (TSS)** – Between May 2010 and April 2013, there were no exceedances of the TSS limitations (**Attachment H**). TSS limits are technology-based requirements for municipal dischargers with secondary treatment required in accordance with 40 CFR Part 133. TSS is a technology-based requirement for municipal dischargers with secondary treatment required in accordance with 40 CFR Part 133. These effluent limits of 30 mg/L (22 kg/d) monthly average and 45 mg/L (34 kg/d) weekly average have been continued from the previous permit.

Eight hour composite samples shall continue to be collected. The TSS data from the last three years during the permit term were evaluated to determine if the facility qualifies for a reduced monitoring frequency. In accordance with Guidance Memo 98-2005, the facility qualifies for a reduced monitoring frequency of 1/week. See **Attachment H** for a summary of the discharge data and a discussion of the criteria for reduced monitoring.

**Biochemical Oxygen Demand (BOD**<sub>5</sub>) -- Between May 2010 and April 2013, there were no exceedances of the BOD<sub>5</sub> limitations (**Attachment H**). Since there have been a decrease in the flow frequencies at the outfall, the new data have been entered into the Regional Water Quality Model for Free Flowing Streams (Version 4.0) to update calculations for BOD<sub>5</sub> limits. A copy of the model output results is found in **Attachment I**. An initial DO concentration of 0 mg/L, a TKN value of 20 mg/L, and 30 mg/L for BOD<sub>5</sub> were used in the model input. The background dissolved oxygen was 7.154 mg/L. The model predicted a dissolved oxygen (DO) sag at the initial discharge point to 7.151 mg/L. This sag is 0.003 mg/L below the existing background condition of 7.154 mg/L. So, these effluent concentrations do not violate the antidegradation policy. Therefore, current treatment limits for BOD<sub>5</sub> are protective of the water quality, and a limit for DO is not needed to meet the DO water quality criterion in 9 VAC 25-260-50 for Class IV receiving waters.

BOD<sub>5</sub> limits are technology-based requirements for municipal dischargers with secondary treatment required in accordance with 40 CFR Part 133. These effluent limits of 30 mg/L (22 kg/d) monthly average and 45 mg/L (34 kg/d) have been continued from the previous permit. In accordance with the VPDES Permit Manual recommendations, BOD<sub>5</sub> shall continue to be monitored via eight-hour composite samples.

The State Water Control Board 1976 Comprehensive Water Resources Plan, Planning Bulletin 205A states that the major point sources of BOD<sub>5</sub> loading, which include a proposed treatment plant for the Town of Pembroke, are not projected to violate the BOD assimilation capacity in the New River through 2020. **Attachment E** contains an excerpt from this planning bulletin.

The BOD<sub>5</sub> data from the last three years during the permit term were evaluated to determine if the facility qualifies for a reduced monitoring frequency. In accordance with Guidance Memo 98-2005, the facility qualifies for a reduced monitoring frequency of 1/week. See **Attachment H** for a summary of the discharge data and a discussion of the criteria for reduced monitoring.

*E. coli* -- Between January 2008 and February 2013, there were no exceedances of the *E. coli* limitation. There were revised Water Quality Standards became effective on February 1,2010, and included updates to the bacteria and disinfection policy in 9 VAC 25-260-170. The Water Quality Standards, 9 VAC 25-260-170, have been revised to indicate that the geometric mean "shall be calculated using all data collected during any calendar month with a minimum of four weekly samples." The limit of 126 cfu/100 mL monthly average has been continued from the previous permit. Grab samples shall be collected 3 days/week between 10 AM and 4 PM.

#### C. Effluent Limitation Evaluation for Toxic Pollutants

In addition to the standard limitations, the discharge must be evaluated to determine whether there is a reasonable potential for the effluent to violate the water quality standards (WQSs) adopted by the State Water Control Board (9 VAC 25-260 et. seq). A summary of the effluent pesticides, semivolatiles, volatiles, and metal data are summarized in **Attachment F**. With the exception of hydrogen sulfide, total copper, and total zinc, none of the pollutant data submitted was above the quantification levels. For each of these parameters, the acute and chronic antidegradation wasteload allocations and effluent data have been input into the STATS program. The program output indicates that permit limits are not needed for hydrogen sulfide, total copper, or total zinc. A copy of the STATS program results is included in **Attachment G**.

Ammonia – Since there have been a decrease in the flow frequencies at the outfall and changes in the temperature and pH, the need for an ammonia limit has been reassessed. The acute and chronic AWLAs and the effluent data were used as input in the Agency's STATS program to determine if limits were necessary for ammonia. For ammonia, a default value of 9.0 mg/L was used as the program input in accordance with Agency

guidance. The program output indicates that permit limits are not necessary for ammonia. A copy of the STATS program result for ammonia is included in **Attachment G**.

**Total Residual Chlorine (TRC)** – The facility uses ultraviolet light as the disinfection method. In the event that the permittee decides to use TRC as an alternative method of disinfection methods, TRC limits have been established to avoid any future modifications to the permit. These limits are included in Part I.B of the permit. In the absence of TRC data, one data value, equal to the QL, was assumed to exist. This methodology is similar to that discussed in Guidance Memo 00-2011 for ammonia. Antidegradation wasteload allocations (AWLAs) have been established for TRC to protect the receiving stream from degradation. Since no data exist for the Tier 2 receiving stream, the baseline is equal to 25 percent of the criterion.

The TRC limits in the previous permit were reassessed with the AWLAs that were determined from revised temperature, pH, and stream flow frequencies. Based on the acute and chronic AWLAs and the Agency's STATS program, permit limits of 0.12 mg/L monthly average and 0.14 mg/L weekly average are needed in the permit. These more stringent limits replace the previous permit limits. In accordance with the VPDES Permit Manual, effluent TRC shall be monitored 3/day at 4 hour intervals via grab samples.

PCBs – PCB congener effluent testing was completed by the permittee on August 20, 2002. The data were below the quantification level of 1.0 μg/L. However, DEQ has developed a water quality criterion of 0.0017 μg/L (9VAC25-260-140) which is significantly below this quantification level. EPA Testing Method 1668A is capable of achieving a quantifications level below this water quality criteria. In addition, the Virginia Department of Health has established a fish consumption advisory for carp and catfish in the New River. So, this segment of the New River does not achieve the fishable designated use defined in 9 VAC 25-260-10 of the Water Quality Standards. Guidance Memo 09-2001 provides the PCB monitoring protocol for TMDL development. PCB monitoring for outfall 001 is included in a permit special condition (Part I.C.14). In accordance with Guidance Memo 09-2001, one wet weather sample and one dry weather sample shall be required. See Attachment E of the PCB impaired waters fact sheet.

- 17. <u>Basis for Sludge Use and Disposal Requirements:</u> Since the facility hauls dewatered sludge to a landfill, there are no sludge limits or monitoring requirements.
- 18. <u>Antibacksliding Statement:</u> Since there are no limitations less stringent than the previous permit, the permit limits comply with the antibacksliding requirements of 9 VAC 25-31-220 L of the VPDES Permit Regulation.
- 19. **Compliance Schedules:** There are no compliance schedules included in this permit.

## 20. **Special Conditions:** A brief rationale for each special condition contained in the permit is given below.

## A. Total Residual Chlorine (TRC) Limitations and Monitoring Requirements (Part I.B)

Rationale: Should the permittee elect to disinfect by chlorine rather than UV light, this condition establishes TRC concentration limits after chlorine contact and final TRC effluent limits and monitoring requirements. This condition is in accordance with chlorine criteria in 9 VAC 25-790 of the Sewage Collection and Treatment Regulations. Also, 40 CFR 122.41(e) requires the permittee, at all times, to properly operate and maintain all facilities and systems of treatment in order to comply with the permit. These requirements ensure proper operation of chlorination equipment to maintain adequate disinfection.

#### B. Compliance Reporting (Part I.C.1)

Rationale: In accordance with VPDES Permit Regulation, 9 VAC 25-31-190 J4 and 220 I, DEQ is authorized to establish monitoring methods and procedures to compile and analyze data. This condition is necessary when pollutants are monitored by the permittee and a maximum level of quantification and/or specific analytical method is required in order to assess compliance with a permit limit or to compare effluent quality with a numeric criterion. This condition also establishes protocols for calculation of reported values.

#### C. 95% Capacity Reopener (Part I.C.2)

Rationale: This condition requires that the permittee address problems resulting from high influent flows, in a timely fashion, to avoid non-compliance and water quality problems from plant overloading. This requirement is contained in 9 VAC 25-31-200 B4 for all POTW and PVOTW permits.

#### D. Indirect Dischargers (Part I.C.3)

Rationale: This condition is required by VPDES Permit Regulation, 9 VAC 25-31-200 B1 for POTWs and PVOTWs that receive waste from someone other than the owner of the treatment works.

#### E. CTC, CTO Requirement (Part I.C.4)

<u>Rationale:</u> This condition is required by Code of Virginia § 62.1-44.19 and the Sewage Collection and Treatment Regulations, 9 VAC 25-790.

#### F. Operations and Maintenance Manual Requirement (Part I.C.5)

• <u>Rationale:</u> An Operations and Maintenance Manual is required by the Code of Virginia § 62.1-44.19, the Sewage Collection and Treatment Regulations, 9 VAC 25-790; and the VPDES Permit Regulation, 9 VAC 25-31-190 E.

#### G. Licensed Operator Requirement (Part I.C.6)

<u>Rationale:</u> The VPDES Permit Regulation, 9 VAC 25-31-200 C, Code of Virginia 54.1-2300 et seq., and Rules and Regulations for Waterworks and Wastewater Works Operators (18 VAC 160-20-10 et seq.) require licensure of operators. A Class III operator is required for this facility.

#### H. Reliability Class (Part I.C.7)

<u>Rationale:</u> A Reliability Class II has been assigned to this facility. Reliability class designations are required by Sewage Collection and Treatment Regulations, 9 VAC 25-790-70 for all municipal facilities.

#### I. Effluent Monitoring Frequencies (Part I.C.8)

Rationale: Permittees are granted a reduction in monitoring frequency based on a history of permit compliance. To remain eligible for the reduction, the permittee should not have violations related to the effluent limits for which reduced frequencies were granted. If the permittee fails to maintain the previous level of performance, the baseline monitoring frequency should be reinstated for those parameters that were previously granted a monitoring frequency reduction.

#### J. Sludge Reopener (Part I.C.9)

<u>Rationale:</u> This condition is required by VPDES Permit Regulation, 9 VAC 25-31-220 C for all permits issued to treatment works treating domestic sewage to allow incorporation of any applicable standard for sewage sludge use or disposal promulgated under section 405(d) of the Clean Water Act.

#### K. Sludge Use and Disposal (Part I.C.10)

Rationale: VPDES Permit Regulation, 9 VAC 25-31-100 P; 220 B2; and 420 and 720, and 40 CFR Part 503 require all treatment works treating domestic sewage to submit information on sludge use and disposal practices and to meet specified standards for sludge use and disposal. Technical requirements may be derived from the VPA Permit Regulation, 5 VAC 5-32-et seq. This special condition, in accordance with Guidance Memo 97-004, clarifies that the Sludge Management Plan approved with the reissuance of this permit is an enforceable condition of the permit.

#### L. Total Maximum Daily Load (TMDL) Reopener (Part I.C.11)

Rationale: Section 303(d) of the Clean Water Act requires that Total Maximum Daily Loads (TMDLs) be developed for streams listed as impaired. This special condition is to allow the permit to be reopened if necessary to bring it into compliance with any applicable TMDL approved for the receiving stream. The reopener recognizes that, according to Section 402(o)(1) of the Clean Water Act, limits and/or conditions may be either more or less stringent than those contained in this permit. Specifically, they can be relaxed if they are the result of a TMDL, basin plan, or other wasteload allocation prepared under Section 303 of the Act.

#### M. Treatment Works Closure Plan (Part I.C.12)

<u>Rationale:</u> In accordance with State Water Control Law § 62.1-44.19, this condition is used to notify the owner of the need for a closure plan where a treatment works is being replaced or is expected to close.

#### N. Permit Application Requirement (Part I.C.13)

Rationale: VPDES Permit Regulation, 9 VAC 25-31-100.D and 40 CFR 122.21(d)(1) require submission of a new application at least 180 days prior to expiration of the existing permit. In addition, the VPDES Permit Regulation, 9 VAC 25-31-100 E.1 and 40 CFR 122.21 (e)(1) note that a permit shall not be issued before receiving a complete application.

## O. Polychlorinated Biphenyl (PCB) Total Maximum Daily Load (TMDL) Development (Part I.C.14)

<u>Rationale</u>: This special condition requires the permittee to monitor and report PCB concentrations in dry weather and wet weather effluent samples consistent with 9 VAC 25-260-280. The results from this monitoring shall be used to develop a PCB TMDL for the New River.

#### P. Significant Discharger Survey (Part I.D)

<u>Rationale:</u> VPDES Permit Regulation, 9 VAC 25-31-730 through 900, and 40 CFR Part 403 require certain existing and new sources of pollution to meet specified regulations.

#### Q. Conditions Applicable to All VPDES Permits (Part II)

<u>Rationale:</u> VPDES Permit Regulation, 9 VAC 25-31-190 requires all VPDES permits to contain or specifically cite the conditions listed.

#### 21. Changes to the Permit:

A. The following special condition has been deleted from the permit:

The Water Quality Standards Monitoring Special Condition (Part I.C.11) has been removed from the permit because the data have been submitted.

- B. Special conditions that have been modified from the previous permit are listed below: (The referenced permit sections are for the new permit.)
  - 1. The Total Residual Chlorine (TRC) Limitations and Monitoring Requirements Special Condition (Part I.B) has been revised to include update TRC limitations.
  - 2. A Compliance Reporting Special Condition (Part I.C.1) has been revised to include information about significant figures.
  - 3. The Operations and Maintenance Manual Special Condition (Part I.C.5) has been revised in accordance with the VPDES Permit Manual.

#### C. The following new special conditions added to the permit are listed below:

- 1. The Effluent Monitoring Frequencies Special Condition (Part I.C.8) has been to require that the permittee's reduced monitoring frequencies revert back to the previous frequencies if they are issued a Notice of Violation for any of the parameters with reduced monitoring.
- 2. A Treatment Works Closure Plan Special Condition (Part I.C.12) has been added in accordance with the VPDES Permit Manual to provide requirements in the event the facility is closed.
- 3. A Permit Application Requirement Special Condition (Part I.C.13) has been added to provide the specific due date for the required submittal of the application.
- 4. A Polychlorinated Biphenyl (PCB) Total Maximum Daily Load (TMDL)
  Development Special Condition (Part I.C.14) has been added to require PCB
  monitoring for use in the development of a PCB TMDL.
- 5. A Significant Discharger Survey Special Condition (Part I.D) has been added to require submission of an annual survey of industrial users into the treatment plant.
- D. **Permit Limits and Monitoring Requirements:** See Table III on page 17 for details on changes to the effluent limits and monitoring requirements.

- 22. Variances/Alternate Limits or Conditions: No variances or alternate limits or conditions are included in this permit. For the previous permit term, the permittee had requested that the 8-hour composite data for TSS and BOD<sub>5</sub> collected during the permit term be used on the application in lieu of 24-hour composite samples. A waiver was requested to allow one pollutant scan instead of 3 samples for ammonia as nitrogen, TKN, and oil and grease. The permittee requested a waiver for phosphorus, total dissolved solids, nitrate plus nitrite nitrogen, and total residual chlorine. Since the receiving stream is not a public water supply or nutrient enriched there are no applicable water quality criteria for phosphorus, total dissolved solids, or nitrate plus nitrogen. Since the facility uses UV rather than chorine for disinfection, total residual chlorine data are not applicable to this facility. These waivers were approved on March 8, 2013. The waivers are consistent with current permit requirements, and therefore the approved waivers have been applied to this reissuance application.
- 23. Regulation of Treatment Works Users: The VPDES Permit Regulation, 9 VAC 25-31-280 B9, requires that every permit issued to a treatment works owned by a person other than a state or municipality provide an explanation of the Board's decision on the regulation of users. The Town of Pembroke, a municipality, owns this treatment works; therefore this regulation does not apply. The permit requires that the facility submit a Significant Industrial Survey (Part I.D).

#### 24. Public Notice Information required by 9 VAC 25-31-290 D:

All pertinent information is on file and may be inspected, and arrangements made for copying by contacting Becky L. France at:

Virginia DEQ Blue Ridge Regional Office 3019 Peters Creek Road Roanoke, VA 24019 540-562-6700 becky.france@deq.virginia.gov

Persons may comment in writing or by e-mail to the DEQ on the proposed permit action and may request a public hearing during the comment period. Comments shall include the name, address, and telephone number of the writer, and shall contain a complete, concise statement of the factual basis for comments. Only those comments received within this period will be considered. The DEQ may decide to hold a public hearing if public response is significant. Requests for public hearings shall state the reason why a hearing is requested, the nature of the issues proposed to be raised in the public hearing, and a brief explanation of how the requester's interests would be directly and adversely affected by the proposed permit action.

Following the comment period, the DEQ will make a determination regarding the proposed permit action. This determination will become effective, unless the DEQ grants a public hearing. Due notice of any public hearing will be given. See **Attachment J** for a copy of the public notice.

25. 303(d) Listed Segments (TMDL): This facility discharges directly to the New River. The stream segment receiving the effluent is listed in part I of the 303(b) list for nonattainment of human health water quality standards from ingestion of PCBs found in fish tissue. The impairment begins at the I-77 bridge crossing the New River and extends downstream to the VA/WVA state line and includes tributaries of Peak and Reed Creek. A PCB TMDL is scheduled for development by 2014. This permit contains a PCB monitoring special condition (Part I.C.14) for TMDL development. A TMDL reopener special condition (Part I.C.11) has also been included in case a future PCB TMDL contains a wasteload allocation for the facility.

#### 26. Additional Comments:

A. Reduced Effluent Monitoring: In accordance with Guidance Memo 98-2005, all permit applications received after May 4, 1998, are considered for reduction in effluent monitoring frequency. Only facilities having exemplary operations that consistently meet permit requirements may qualify for reduced monitoring. To qualify for consideration of reduced monitoring requirements, the facility should not have been issued any Warning Letters, Letter of Noncompliance (LON) or Notices of Violation (NOV), or be under any Consent Orders, Consent Decrees, Executive Compliance Agreements, or related enforcement documents during the past three years.

The facility has not received any warning letters or NOVs. A DEQ compliance inspection conducted on December 13, 2011 identified some deficiencies related to clerical errors, calculation errors, needed updates to the Operations and Maintenance Manual, requested testing documentation, and reported a flow meter out of paper. According to a letter dated February 21, 2012, Pembroke WWTP took steps to address all of these deficiencies. A DEQ compliance inspection conducted on April 26, 2013 identified a need for increased maintenance and operation controls for solids removal and disinfection redundancy. In a letter dated April 30, 2013, the permittee noted completion of the requested operational controls. There are no outstanding compliance or enforcement issues at this treatment facility. Therefore, the permittee qualifies for a reduced monitoring data evaluation.

- B. Previous Board Action: None
- C. **Staff Comments:** The discharge is not controversial, and is conformance with the existing planning document for the area. The permit is being reissued for a period of slightly less than five years to even out the DEQ staff permitting workload.

The Department of Conservation and Recreation's Division of Natural Heritage (DCR) has identified natural heritage resources in the project area. The candy darter and hellbender have been historically documented in the New River. DCR commented that habitat alteration from impoundments or channelization and water pollution threatens hellbenders. DCR supports the use of UV disinfection at this facility. The facility currently uses UV disinfection and is required to dechlorinate if they decide to use chlorine disinfection in the future.

#### Fact Sheet VA0088048 Page 15 of 17

On August 13, 2013 the schedule for submission of PCB data in Part I.C.14 of the permit was revised to provide the data earlier for use in the TMDL study of the New River.

D. Public Comments: No comments were received during the public comment period.

#### E. Tables

Table I Discharge Description (Page 2)
Table II Basis for Monitoring Requirements (Page 16)
Table III Permit Processing Change Sheet (Page 17)

#### F. Attachments

- A. Flow Frequency Memorandum
- B. Wastewater Schematic
- C. Site Inspection Report
- D. USGS Topographic Map
- E. Ambient Water Quality Information
  - STORET Data (Station 9-NEW030.15)
    - STORET Data (Station 9-NEW056.22)
    - 2010 Impaired Waters Summary (Excerpt)
    - 1976 New River Basin Comprehensive Water Resources Plan (Excerpt)
    - Endangered Species Information
- F. Effluent Data
- G. Wasteload and Limit Calculations
  - Mixing Zone Calculations (MIXER)
  - Antidegradation Wasteload Allocation Spreadsheet
  - STATS Program Results
- H. Reduced Monitoring Evaluation Memorandum
- I. Regional Water Quality Model (Version 4.0)
- J. Public Notice
- K. EPA Checksheet

#### Table II BASIS FOR LIMITATIONS - MUNICIPAL

( ) Interim Limitations

(x ) Final Limitations

OUTFALL: 001

DESIGN CAPACITY: 0.20 MGD

Effective Dates - From: Effective Date

To: Expiration Date

	·		MONITORING REQUIREMENTS					
PARAMETER	BASIS FOR LIMITS	Monthly Average	Weekly Average	Minimum	Maximum	Frequency	Sample Type	
Flow (MGD)	NA	NL	NA	NA	NL	Continuous	TIRE	
pH (Standard Units)	1,2	NA	NA	6.0	9.0	1/Day	Grab	
BOD₅	1	30 mg/L 22 kg/d	45 mg/L 34 kg/d	NA	NA	1/Week	8 HC	
Total Suspended Solids	1	30 mg/L 22 kg/d	45 mg/L 34 kg/d	NA -	NA	1/Week	8 HC	
E. coli	2	126 cfu/100 mL (geometric mean)	. NA	NA	NA .	3 Days/Week (between 10 am and 4 pm)	Grab	

NA = Not Applicable

NL = No Limitations; monitoring only

8HC= 8 hour composite

TIRE = totalizing, indicating, recording equipment

The basis for the limitations codes are:

- Federal Technology-Based Secondary Treatment Regulation (40 CFR Part 133) 1.
- Water Quality Criteria 2.

## **Table III**PERMIT PROCESSING CHANGE SHEET

#### LIMITS AND MONITORING SCHEDULE:

Outfall	Parameter	_	Requirement ngcđ	Effluent Lim	nits Changed	Reason for Change	Date
No.	Changed	From	То	From	To.		
001	BOD <sub>5</sub>	3 Days/Week	1/Week			Monitoring data supports a reduced monitoring frequency of 1/week.	3/20/13
001	TSS	3 Days/Week	1/Week			Monitoring data supports a reduced monitoring frequency of 1/week.	3/20/13
100	E. coli (applicable when ultraviolet used as disinfection)	1/Week	3 Days/Week			Monitoring frequency increased in accordance with VPDES Permit Manual.	3/20/13
001	Total Residual Chlorine (only applicable if chlorine used for disinfection)	1/Day	3/Day at 4 hour intervals	0.13 mg/L monthly average and 0.16 mg/L weekly average	0.12 mg/L monthly average and 0.14 mg/L weekly average	STATS program determined that more stringent limits were needed to protect water quality of the receiving stream. The monitoring frequency increased in accordance with VPDES Permit Manual.	3/20/13

# Attachment A Flow Frequency Memorandum

#### **MEMORANDUM**

## DEPARTMENT OF ENVIRONMENTAL QUALITY - WATER DIVISION 3019 Peters Creek Road, Roanoke, Virginia 24019

**SUBJECT:** Flow Frequency Determination

Pembroke WWTP – Reissuance (VA0088048)

TO:

Permit File

FROM:

Becky L. France, Water Permit Writer B

DATE:

March 19, 2013

This memorandum supercedes the July 30, 2008 memorandum concerning the subject VPDES permit. Pembroke WWTP discharges to the New River near Pembroke, Virginia. Stream flow frequencies are required at this site to develop effluent limitations for the VPDES permit.

The USGS has operated a continuous record gauge on the New River near Eggleston, Virginia (#30171500) from 1915 to 1976. The gauge is located at the Route 730 bridge in Eggleston, Virginia. Flow has been regulated at the gauge by Claytor Reservoir since 1940. This gauge is located approximately 4 miles upstream of the discharge point. The nearest downstream continuous record gauge on the New River is located at Glen Lyn, Virginia (#03176500), and has been operating since 1927. There are several discharges and withdrawals between the discharge point and the Glen Lyn gauge.

Since there is no current flow information for the Eggleston, Virginia gauge, flow frequencies for the gauge were determined by calculating a ratio of the Glen Lyn and Eggleston gauge data from the same period of record (1940-1976) and multiplying the ratio by the current flow frequencies at Glen Lyn. To solve for the flow frequencies at the discharge point, a ratio of the drainage area of the gauge (Eggleston) and the discharge point were used to calculate the flow at the discharge point.

The high flow months are January through May. The flow frequencies for the discharge point are listed on the attached table.


Flow Frequency Determination: Pembroke WWTP

				Г в Т		F	G	H H	l i	J	Т к Т	1	м
	Α	В	С	D	E	<u> </u>	<u> </u>	П	<u> </u>	J			IVI
2			<u> </u>				<u></u>						
3		— ··· · <del>—</del>	<del>_</del>	<u> </u>			<u> </u>	<u> </u>					
4	·							<del> </del> -					
5		<del>-</del>	-	<del>                                     </del>			<del></del>	<del>                                     </del>		-			
	Reference	Gauge (dat	! ta from 1940	to 1976)			1	Flow frequ	lencies for	the reissued permi	t (11/16/13)		
7			n, VA (#031		<del></del>				at Dischar				
8			rea [ mi²] =							Area [ mi²] =	3.035		
9		ft <sup>3</sup> /s	MGD	2,55	ft <sup>3</sup> /s	MGD			ft <sup>3</sup> /s	MGD	2,333	ft <sup>3</sup> /s	MGD
10	1Q10 =	701	453	High Flow 1Q10 =	959	620		1Q10 =		407	High Flow 1Q10 =	928	600
11	7Q10 =	883	571	High Flow 7Q10 =	1,285	830		7Q10 =		486	High Flow 7Q10 =	1,294	836
12	30Q5 =	1,184	765	HM =	2,575	1,664		30Q5 =		708	HM =	2,484	1,605
13	30Q10=	1,041	673	High Flow 30Q10=	1,751	1,132		30Q10=		600	High Flow 30Q10=	1,682	1,087
14		·			· · · ·		<u> </u>						
15				<del></del>	-							-	
16	Reference	Gauge (dat	a from 1940	to 1976)			<u> </u>			wat Eggleston (data	from 1940 to 2011)		
17	New River	at Glen Lyr	ı, VA (#0317	6500)				New River	at Egglesto	on, VA (#03171500)			
18		Drainage A	\rea [ mi <sup>2</sup> ] =	3,783					Drainage A	\rea [ mi²] =	2,961	'	
19		ft <sup>3</sup> /s	MGD		ft <sup>3</sup> /s	MGD			ft <sup>3</sup> /s	MGD		ft <sup>3</sup> /s	MGD
20	1Q10 =	1,001	647	High Flow 1Q10 =	1,250	808		1Q10 =	615	397	High Flow 1Q10 =	905	585
21	7Q10 =	1,218	787	High Flow 7Q10 =	1,629	1,053		7Q10 =	734	474	High Flow 7Q10 =	1,262	816
22	30Q5 =	1,490	963	HM =	3,188	2,060		30Q5 =		691	HM =	2,423	1,566
23	30Q10=	1,370	885	High Flow 30Q10=		0	<u> </u>	30Q10=	905	585	High Flow 30Q10=	1,641	1,061
24							<u>i.</u>						
25							<u> </u>						
			ta from 1940										
27			ı, VA (#0317								- · · · · ·		
28			\rea [ mi²] =	3,783	2								
29	. <u></u>	ft <sup>3</sup> /s	MGD		ft <sup>3</sup> /s	MGD							
30	1Q10 =	878	567	High Flow 1Q10 =	1,180	763							
31	7Q10 =	1,012	654	High Flow 7Q10 =	1,600	1,03 <u>4</u>				<u> </u>	<u> </u>		
32	30Q5 =	1,345	869	HM =	3,000	1,939	ļ			<u> </u>			
33	30Q10=	1,191	770	High Flow 30Q10=	2,160	1,396	<u> </u>			<del></del>	<u> </u>		
34	├		<b> </b>	<del> </del>	<del></del>		<del> </del> -			<u>:</u>	<u> </u>		
35 36	- <del></del>		<del></del>			<u> </u>	<del>                                     </del>	<u> </u>	<del>                                     </del>	·			
	No high flo	** 30010 4	ata available	for Reference Station 0	2176500 6	r 1040 107	'6 co ratio	for high flow	30010				
				same as for the low flow		л 1940-197 	0, 50 (800	ioi iligii ilow	300(10		- <del>1</del>		
30	Iyauye stati	יווט מסטטווו	ea to be the	Same as for the low how	JUGIU.	<u> </u>		1	<u> </u>	·	<u> </u>		

SITEID	NAME	RECORD	LATLONG	DAAREA	HARMEAN	HF30Q10	HF7Q10	HF1Q10	Z30Q5	Z30Q10	Z7Q10	Z1Q10	Z1Q30	HFMTHS	Statperiod	Yrstrn	NOTES.
	New River at Eggleston, Va.	R, 1915-76	Lat 37 17'22", Long 80 37'00", NAD 83	2961	2575	1751	1285	959	1184	1041	883	701		JAN-MAY	1940-1976		Flow Regulated since 1939 by Claytor Reservoir
	New River at Glen Lyn, Va.	R, 1927-	Lat 37 22'22", Long 80 51'38", NAD 83	3783	3000	2160	1600	1180	1345	1191	1012	878	790	JAN-MAY	1940-2011	•	Flow Regulated since 1939 by Claytor Reservoir

## Attachment B

**Wastewater Schematic** 



Attachment C
Site Inspection Report

#### MEMORANDUM

#### DEPARTMENT OF ENVIRONMENTAL QUALITY Blue Ridge Regional Office

3019 Peters Creek Road

Roanoke, VA 24019

SUBJECT:

Site Inspection Report for Pembroke WWTP

Reissuance of VPDES Permit No. VA0088048

TO:

Permit File

FROM:

Becky L. France, Water Permit Writer

DATE:


April 16, 2013

On April 16, 2013, a site inspection of the Pembroke WWTP was conducted. Mr. Stanley Lucas, operator, was present at the inspection.

Pembroke WWTP consists of a comminutor, bar screen, grit chamber, two oxidation ditches, two clarifiers, ultraviolent disinfection system, cascade aerator, two aerobic digesters, and four sludge drying beds. The facility is currently operating only one of the oxidation ditches. This 0.20 MGD facility began operation in 1996.


Wastewater enters the plant from a 6-inch force main and flows through a comminutor chamber and manual bar screen channel. Then, the wastewater passes through a grit removal chamber. Grit is removed to a sump for dewatering. At the time of the site visit, the grit chamber was not operational. The wastewater then flows to an oxidation ditch which is aerated by an aeration rotor assembly. Due to low effluent flows, only the inner oxidation ditch is currently used. At the time of the site visit, the wastewater had a chocolate color. From the oxidation ditch the wastewater enters two parallel clarifiers. There were no visible solids being carried over the weir. From the clarifier, the wastewater overflows the weir and is routed to one of the two ultraviolent light banks. Disinfected effluent flows through a trough into a cascade aerator and is discharged into the New River. A flow meter continuously records effluent flow within a Parshall flume which is located at the end of the trough. At the time of the site visit, the cascade steps were clean, and the effluent appeared clear.

Sludge that is collected in the clarifiers is periodically pumped to the aerated aerobic digesters. The digesters' coarse bubble air diffuser system operates on a timer. Sludge is removed from the digesters by sludge pumps and transferred to the four sludge drying beds. A blanket of sludge is applied to the covered sludge drying beds. Underdrainage from the sludge drying beds and decant from the sludge digester are returned to the oxidation ditch. The caked sludge, which should be at least 20 percent solids, is removed and disposed of in a landfill. According to Mr. Lucas, sludge is currently being hauled to the landfill approximately once a month.



Attachment D

US Topographic Map



#### Attachment E

### **Ambient Water Quality Information**

- STORET Data (Station 9-NEW030.15)
- STORET Data (Station 9-NEW056.22)
- 2010 Impaired Waters Summary (Excerpt)
- 1976 New River Basin Comprehensive Water Resources Plan (Excerpt)
- Endangered Species Information

#### VAW-N29R 9-NEW030.15

02/12/2004 10:25         8.17           04/27/2004 10:00         8.12           06/15/2004 09:30         7.65           08/25/2004 11:00         8.2           10/26/2004 11:40         7.81           12/16/2004 10:40         7.86           02/15/2005 11:40         7.63           04/13/2005 10:25         7.75           06/14/2005 10:30         7.8           08/15/2005 10:15         8.4           10/18/2005 11:00         8.04           12/13/2005 10:45         6.8           02/09/2006 09:30         8.1           04/11/2006 10:10         7.4           08/15/2006 10:45         8           12/11/2006 11:25         8.1           01/18/2007 11:00         8.2           03/27/2007 11:50         7.1           05/17/2007 10:50         7.7           07/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         7.1           07/9/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7.           01/28/2010 11:40	Collection Data Time	L-U (C II)
04/27/2004 10:00	Collection Date Time	pH (S.U.)
06/15/2004 09:30         7.65           08/25/2004 11:00         8.2           10/26/2004 11:40         7.81           12/16/2004 10:40         7.86           02/15/2005 11:40         7.63           04/13/2005 10:25         7.75           06/14/2005 10:30         7.8           08/15/2005 10:15         8.4           10/18/2005 11:00         8.04           12/13/2005 10:45         6.8           02/09/2006 09:30         8.1           04/11/2006 10:10         7.4           08/15/2006 10:45         8           12/11/2006 11:25         8.1           01/18/2007 11:00         8.2           03/27/2007 11:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         7.2           11/19/2008 09:25         7.1           07/21/2009 11:25         6.5           03/10/2009 09:25         7.           05/12/2009 11:25         6.5           03/10/2009 09:25		
08/25/2004 11:00		
10/26/2004 11:40       7.81         12/16/2004 10:40       7.86         02/15/2005 11:40       7.63         04/13/2005 10:25       7.75         06/14/2005 10:30       7.8         08/15/2005 10:15       8.4         10/18/2005 11:00       8.04         12/13/2005 10:45       6.8         02/09/2006 09:30       8.1         04/11/2006 10:10       7.4         08/15/2006 10:45       8         12/11/2006 11:25       8.1         01/18/2007 11:00       7.4         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       7.2         11/19/2008 09:25       7.1         07/09/2008 12:20       7.4         09/02/2009 11:25       6.5         03/10/2009 09:25       7.         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       7         05/26/2010 11:45       8.1		i
12/16/2004 10:40       7.86         02/15/2005 11:40       7.63         04/13/2005 10:25       7.75         06/14/2005 10:30       7.8         08/15/2005 10:15       8.4         10/18/2005 11:00       8.04         12/13/2005 10:45       6.8         02/09/2006 09:30       8.1         04/11/2006 10:10       7.4         08/15/2006 10:45       8         12/11/2006 11:25       8.1         01/18/2007 11:00       7.4         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7.         05/12/2009 13:40       8.1         07/21/2009 13:40       8.1         07/21/2009 11:25       6.8         03/24/2010 11:40       7         01/28/2010 11:40       7         01/28/2010 11:45       8.1		· ·
02/15/2005 11:40	10/26/2004 11:40	7.81
04/13/2005 10:25		7.86
06/14/2005 10:30         7.8           08/15/2005 10:15         8.4           10/18/2005 11:00         8.04           12/13/2005 10:45         6.8           02/09/2006 09:30         8.1           04/11/2006 10:10         7.4           08/15/2006 10:45         8           12/11/2006 11:25         8.1           01/18/2007 11:00         8.2           03/27/2007 11:50         7.1           05/17/2007 10:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         8.1           07/09/2008 12:20         7.4           09/02/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7           05/12/2009 11:40         7           07/21/2009 11:40         7           01/28/2010 09:50         8           03/24/2010 11:40         8.2           05/26/2010 11:45         8.5           01/18/2011 14:25         7.9<	02/15/2005 11:40	7.63
08/15/2005 10:15         8.4           10/18/2005 11:00         8.04           12/13/2005 10:45         6.8           02/09/2006 09:30         8.1           04/11/2006 10:10         7.4           08/15/2006 10:45         8           12/11/2006 11:25         8.1           01/18/2007 11:00         8.2           03/27/2007 11:50         7.1           05/17/2007 10:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7           05/12/2009 11:40         7           07/21/2009 11:40         7           01/28/2010 09:50         8           03/24/2010 11:40         7           01/28/2010 11:45         8.1           09/02/2010 12:15         8.1           09/02/2010 12:15         8.1           09/02/2011 12:20         7.4           05/05/2011 13:45         7.7 <td>04/13/2005 10:25</td> <td>7.75</td>	04/13/2005 10:25	7.75
10/18/2005 11:00       8.04         12/13/2005 10:45       6.8         02/09/2006 09:30       8.1         04/11/2006 10:10       7.4         08/15/2006 10:45       8         12/11/2006 11:25       8.1         01/18/2007 11:00       8.2         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       7         01/28/2010 11:45       8.1         09/02/2010 12:15       8.1         09/02/2010 11:45       8.5         01/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7 <t< td=""><td>06/14/2005 10:30</td><td>7.8</td></t<>	06/14/2005 10:30	7.8
12/13/2005 10:45       6.8         02/09/2006 09:30       8.1         04/11/2006 10:10       7.4         08/15/2006 10:45       8         12/11/2006 11:25       8.1         01/18/2007 11:00       8.2         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       7.9         05/20/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         <	08/15/2005 10:15	8.4
02/09/2006 09:30         8.1           04/11/2006 10:10         7.4           08/15/2006 10:45         8           12/11/2006 11:25         8.1           01/18/2007 11:00         8.2           03/27/2007 11:50         7.1           05/17/2007 10:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         7.9           05/20/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7.1           07/21/2009 13:40         8.1           07/21/2009 13:40         8.1           07/21/2009 13:40         8.1           07/21/2009 13:40         8.1           07/21/2009 11:05         6.8           09/21/2009 11:05         6.8           09/21/2009 11:40         7           01/28/2010 11:40         7           01/28/2010 11:45         8.1           09/02/2010 12:15         8.1           09/02/2011 12:20         7	10/18/2005 11:00	8.04
04/11/2006 10:10         7.4           08/15/2006 10:45         8           12/11/2006 11:25         8.1           01/18/2007 11:00         8.2           03/27/2007 11:50         7.1           05/17/2007 10:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         7.9           05/20/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7           05/12/2009 13:40         8.1           07/21/2009 13:40         8.1           07/21/2009 13:40         8.1           07/21/2009 09:25         7.7           11/17/2009 11:40         7           01/28/2010 09:50         8           03/24/2010 11:40         7           01/28/2010 11:45         8.1           07/20/2010 12:15         8.1           09/02/2010 11:45         8.5           11/18/2011 14:25         7.9           03/08/2011 12:20         7.4 </td <td>12/13/2005 10:45</td> <td>6.8</td>	12/13/2005 10:45	6.8
08/15/2006 10:45       8         12/11/2006 11:25       8.1         01/18/2007 11:00       8.2         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       7.9         05/20/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 13:40       8.1         07/21/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       7.9         <	02/09/2006 09:30	8.1
12/11/2006 11:25       8.1         01/18/2007 11:00       8.2         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       8.1         07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:25       8.3         11/02/2011 12:45       8.3	04/11/2006 10:10	7.4
01/18/2007 11:00       8.2         03/27/2007 11:50       7.1         05/17/2007 10:50       7.7         07/11/2007 11:35       8         09/11/2007 11:30       8         11/28/2007 11:00       7.5         01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:35       7.9         05/20/2008 12:15       8.1         07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:45       8.1         09/02/2010 12:15       8.1         09/02/2010 12:15       8.1         09/02/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       7.9         04/26/2012 12:15       7.9	08/15/2006 10:45	8
03/27/2007 11:50	12/11/2006 11:25	8.1
05/17/2007 10:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         8.1           07/09/2008 12:15         7.4           09/02/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7           05/12/2009 13:40         8.1           07/21/2009 11:05         6.8           09/21/2009 09:25         7.7           11/17/2009 11:40         7           01/28/2010 09:50         8           03/24/2010 11:40         8.2           05/26/2010 11:45         8.1           09/02/2010 12:15         8.1           09/02/2010 12:15         8.4           01/18/2011 14:25         7.9           03/08/2011 12:20         7.4           05/05/2011 13:45         7.7           07/12/2011 12:25         8.3           11/02/2011 12:45         8.3           01/17/2012 12:25         7.9           04/26/2012 12:15         7	01/18/2007 11:00	8.2
05/17/2007 10:50         7.7           07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         8.1           07/09/2008 12:15         7.4           09/02/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7           05/12/2009 13:40         8.1           07/21/2009 11:05         6.8           09/21/2009 09:25         7.7           11/17/2009 11:40         7           01/28/2010 09:50         8           03/24/2010 11:40         8.2           05/26/2010 11:45         8.1           09/02/2010 12:15         8.1           09/02/2010 12:15         8.4           01/18/2011 14:25         7.9           03/08/2011 12:20         7.4           05/05/2011 13:45         7.7           07/12/2011 12:25         8.3           11/02/2011 12:45         8.3           01/17/2012 12:25         7.9           04/26/2012 12:15         7	03/27/2007 11:50	7.1
07/11/2007 11:35         8           09/11/2007 11:30         8           11/28/2007 11:00         7.5           01/15/2008 13:05         7.9           03/25/2008 12:35         7.9           05/20/2008 12:15         8.1           07/09/2008 12:20         7.4           09/02/2008 12:15         7.2           11/19/2008 09:25         7.1           01/22/2009 11:25         6.5           03/10/2009 09:25         7           05/12/2009 13:40         8.1           07/21/2009 11:05         6.8           09/21/2009 09:25         7.7           11/17/2009 11:40         7           01/28/2010 09:50         8           03/24/2010 11:40         8.2           05/26/2010 11:55         7.8           07/20/2010 12:15         8.1           09/02/2010 11:45         8.1           01/18/2011 14:25         7.9           03/08/2011 12:20         7.4           05/05/2011 13:45         7.7           07/12/2011 12:25         8.3           11/02/2011 12:25         8.3           01/17/2012 12:25         7.9           04/26/2012 12:15         7.9           04/26/2012 12:45         8	05/17/2007 10:50	7.7
11/28/2007 11:00	1	
01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       8.1         07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:25       8.3         11/02/2011 12:25       7.9         04/26/2012 12:15       7.9         04/26/2012 12:45       8.7         08/21/2012 12:40       8.5	09/11/2007 11:30	8
01/15/2008 13:05       7.9         03/25/2008 12:35       7.9         05/20/2008 12:15       8.1         07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:25       8.3         11/02/2011 12:25       7.9         04/26/2012 12:15       7.9         04/26/2012 12:45       8.7         08/21/2012 12:40       8.5	11/28/2007 11:00	7.5
05/20/2008 12:15       8.1         07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       8.3         11/02/2011 12:45       8.3         01/17/2012 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5	01/15/2008 13:05	
05/20/2008 12:15       8.1         07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       8.3         11/02/2011 12:45       8.3         01/17/2012 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5	03/25/2008 12:35	7.9
07/09/2008 12:20       7.4         09/02/2008 12:15       7.2         11/19/2008 09:25       7.1         01/22/2009 11:25       6.5         03/10/2009 09:25       7         05/12/2009 13:40       8.1         07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2010 10:50       8.4         01/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:25       8.3         11/02/2011 12:45       8.3         01/17/2012 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5		-
11/19/2008 09:25	07/09/2008 12:20	7.4
01/22/2009 11:25	09/02/2008 12:15	7.2
01/22/2009 11:25	11/19/2008 09.25	7.1
05/12/2009 13:40 8.1 07/21/2009 11:05 6.8 09/21/2009 09:25 7.7 11/17/2009 11:40 7 01/28/2010 09:50 8 03/24/2010 11:40 8.2 05/26/2010 11:55 7.8 07/20/2010 12:15 8.1 09/02/2010 11:45 8.5 11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:25 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:45 8.7	01/22/2009 11:25	
07/21/2009 11:05       6.8         09/21/2009 09:25       7.7         11/17/2009 11:40       7         01/28/2010 09:50       8         03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2010 10:50       8.4         01/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:45       8.3         11/02/2011 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5	03/10/2009 09:25	7
09/21/2009 09:25 7.7 11/17/2009 11:40 7 01/28/2010 09:50 8 03/24/2010 11:40 8.2 05/26/2010 11:55 7.8 07/20/2010 12:15 8.1 09/02/2010 11:45 8.5 11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:25 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	05/12/2009 13:40	8.1
09/21/2009 09:25 7.7 11/17/2009 11:40 7 01/28/2010 09:50 8 03/24/2010 11:40 8.2 05/26/2010 11:55 7.8 07/20/2010 12:15 8.1 09/02/2010 11:45 8.5 11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:25 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	07/21/2009 11:05	6.8
11/17/2009 11:40 7 01/28/2010 09:50 8 03/24/2010 11:40 8.2 05/26/2010 11:55 7.8 07/20/2010 12:15 8.1 09/02/2010 11:45 8.5 11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	09/21/2009 09:25	7.7
03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2010 10:50       8.4         01/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       8.3         11/02/2011 12:45       8.3         01/17/2012 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5	11/17/2009 11:40	
03/24/2010 11:40       8.2         05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2010 10:50       8.4         01/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       8.3         11/02/2011 12:45       8.3         01/17/2012 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5	1	8
05/26/2010 11:55       7.8         07/20/2010 12:15       8.1         09/02/2010 11:45       8.5         11/18/2010 10:50       8.4         01/18/2011 14:25       7.9         03/08/2011 12:20       7.4         05/05/2011 13:45       7.7         07/12/2011 12:20       8.1         09/20/2011 12:25       8.3         11/02/2011 12:45       8.3         01/17/2012 12:25       7.9         04/26/2012 12:15       7.9         06/25/2012 12:45       8.7         08/21/2012 12:40       8.5	1	
07/20/2010 12:15 8.1 09/02/2010 11:45 8.5 11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5		
09/02/2010 11:45 8.5 11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5		
11/18/2010 10:50 8.4 01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5		
01/18/2011 14:25 7.9 03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	11/18/2010 10:50	
03/08/2011 12:20 7.4 05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5		
05/05/2011 13:45 7.7 07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	03/08/2011 12:20	
07/12/2011 12:20 8.1 09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5		
09/20/2011 12:25 8.3 11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5		
11/02/2011 12:45 8.3 01/17/2012 12:25 7.9 04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	09/20/2011 12:25	
04/26/2012 12:15 7.9 06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	11/02/2011 12:45	
06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	01/17/2012 12:25	7.9
06/25/2012 12:45 8.7 08/21/2012 12:40 8.5	04/26/2012 12:15	7.9
	06/25/2012 12:45	8.7
	08/21/2012 12:40	
10/25/2012 10:40   8.1	10/25/2012 10:40	8.1
12/18/2012 12:35 7.9		
01/15/2013 11:15 7.6	1	

90th Percentile pH 10th Percentile pH 8.3 S.U. 7.1 S.U.

#### VAW-N29R 9-NEW030.15

Callastian Data	11
Collection Date Time	Hardness, Total
	(mg/L as CaCO <sub>3</sub> )
01/28/1999 10:45 02/10/1999 10:45	54 60
	60
03/30/1999 12:40	70 70
04/26/1999 11:10	78
05/10/1999 10:50	60
06/22/1999 11:10	71
07/26/1999 12:00	78.4
08/17/1999 11:20	87.2
09/21/1999 11:30	80.9
10/13/1999 10:40	75.2
11/16/1999 11:30	66.7
12/14/1999 09:30	64.1
01/26/2000 11:00	72.3
02/14/2000 11:25	52.5
03/29/2000 10:20	59
04/06/2000 11:40	47
05/24/2000 11:05	63
06/26/2000 11:30	75.4
07/25/2000 10:00	72.4
08/29/2000 12:00	80
09/26/2000 11:00	82
10/11/2000 12:00	87.1
11/20/2000 10:40	82.6
12/20/2000 10:00	58.9
01/30/2001 08:20	82
02/21/2001 12:50	56.4
03/15/2001 11:00	45
04/16/2001 13:10	30.3
05/08/2001 12:45	61.4
06/21/2001 14:30	61.1
07/17/2001 14:00	98.9
08/15/2001 10:00	69.2
09/11/2001 14:20	43.4
10/25/2001 11:00	60.6
11/27/2001 09:10	57.9
12/18/2001 11:10	68.2
02/25/2002 11:15	36
03/14/2002 10:55	75.5
04/29/2002 13:30	65. <del>9</del>
05/30/2002 12:30	77.3
06/25/2002 11:45	96.9
07/30/2002 09:00	88.7
08/21/2002 10:55	91.3
09/24/2002 13:20	54.4
10/28/2002 14:20	78.2
11/21/2002 09:30	50.5
12/12/2002 10:00	55.3
01/22/2003 11:30	84.5
02/11/2003 11:15	75.1
03/13/2003 14:30	67.5
04/10/2003 11:45	54.9
06/12/2003 11:30	63.1
00/12/2000 11:00	<u> </u>

Mean Hardness 67.8 mg/L

1/23/02 10U 1/23/02 306.3 These data used in data set considered outliers. Route 730 Bridge at Eggleston Gauge (Above Celanese Plant)

Collection Date Time	Temp ( <sup>O</sup> C)
01/26/2000 11:50	0.7
02/14/2000 12:30	4.6
03/29/2000 09:20	7.2
04/06/2000 12:50	13.1
05/24/2000 12:30	19.5
05/24/2000 12:35	19.5
06/26/2000 12:15	25.4
07/25/2000 08:25	20
08/29/2000 11:10	22.4
09/26/2000 08:30	17.5
10/11/2000 11:00	12
11/20/2000 08:00	4.1
12/20/2000 09:00	0.8
01/30/2001 11:30	5.4
02/21/2001 12:00	-8
03/15/2001 08:20	8.4
04/16/2001 12:20	11.9
05/08/2001 14:15	16.8
06/21/2001 13:00	23.1
08/15/2001 08:50	22
10/25/2001 09:30	15.9
12/18/2001 09:50	8.7
02/25/2002 09:30	4.8
04/29/2002 14:00	15.66
06/25/2002 13:05	28.26
08/21/2002 11:20	25.92
10/28/2002 15:00	15
12/12/2002 11:30	5.54
02/11/2003 12:20	3.4
04/10/2003 12:30	9.7
06/12/2003 12:25	19.56
01/18/2007 12:00	4.6
03/27/2007 12:30	13.8
05/17/2007 12:15	17.2
07/11/2007 13:05	24.8
09/11/2007 13:05	24
11/28/2007 12:20	8.3
01/15/2008 13:50	4.7
03/25/2008 13:10	8.6
05/20/2008 13:00	16.2
07/09/2008 14:00	24.1
09/02/2008 13:15	24.2
11/19/2008 10:05	4.2
01/20/2011 13:30	4.3
03/24/2011 12:05	10.9
05/11/2011 13:05	18.4
07/19/2011 13:30	25.1
09/15/2011 13:05	22.5
11/29/2011 14:00	11.6
01/25/2012 14:45	5.5
04/03/2012 14:43	3.5 16
06/19/2012 12:45	23.2
08/22/2012 14:00	23.2 24.1
10/17/2012 13:20	15.7
12/12/2012 14:30	
12/12/2012 14:30	8.1

90th percentile temperature	24.2 °C
90th percentile temperature (Jan May)	17.0 <sup>O</sup> C

VAW-N29R STORET Station 9-NEW030.15

#### **New River PCB Data**

Collection Date Time	PCBs Total, Sediment (ug/kg dry wt.)
7/16/1996 12:35	30U
7/9/1997 12:20	30U
8/12/1998 14:05	100
5/24/2000 11:10	80J

U= Indicates material was analyzed for but not above detection J=Estimated Value

VAW-N29R STORET Station 9-NEW030.15

#### New River Dissolved Metals Data (ug/l)

Collection Date Time	As	Cd	Cr	Cu	Fe	Pb	Mn	TI	Ni	Ag	Zn	Sb	Al		Hg-TL filtered, ultrace metal method NG/L	Hg
10/23/1997 13:00	0.68	<0.1	0.17	1	<10	<0.1	3.4	<0.1	0.44	<0.1	<1	<0.1	3.4	<0.5		<0.2
6/26/2001 10:00					<50	U		<0.2	U						<1.5	-0.2

- ---



## 2010 Impaired Waters

## Categories 4 and 5 by DCR Watershed\*

#### New River Basin

Fact Sheet prepared for DCR Watershed: N29\*

Cause Group Code: N29R-01-PCB

New River, Claytor Lake, Peak Creek, Reed Creek and Stony Creek

Location: The impairment begins at the I-77 bridge crossing the New River and extends downstream to the VA/WVA State Line

and includes the tributaries Peak Creek, Reed Creek and Stony Creek as described below.

City / County: Giles Co.

Montgomery Co.

Pulaski Co.

Radford City

Use(s):

Fish Consumption

Cause(s) /

VA Category: PCB in Fish Tissue/ 5A

The Virginia Department of Health (VDH) issued a fish consumption advisory on August 6, 2001 for polychlorinated biphenyls (PCBs) for the lower portion of the New River (Rt. 114 Bridge downstream to the VA / WVA State Line - 52.0 miles) based on fish tissue collections from Carp. An Advisory extension to Claytor dam was issued 8/06/2003 (11.47 miles) recommends that no carp be consumed in these waters and no more than two meals per month of flathead and channel catfish. The VDH PCB Fish Consumption Advisory was further extended upstream on the New River (13 miles) to the I-77 Bridge to include the lower portions of Peak Creek (4.02 miles), Reed Creek (16.35 miles) and Claytor Lake (4,287 acres) on 12/02/2004. The VDH advises consumption should not exceed two meals per month for carp and smallmouth bass. The VDH level of concern is 50 parts per billion (ppb) in fish tissue.

There are eight fish tissue collection sites within the 2010 data window reporting exceedances of the WQS based 20 ppb fish tissue value (TV) (VDH 50 ppb). These data are reviewed by the VDH in making an advisory determination. A complete listing of collection sites and associated fish tissue data are available at http://www.deq.virginia.gov/fishtissue/fishtissue.html. A more detailed presentation of the data can also be found using an interactive mapping application at http://gisweb.deq.state.va.us/. The VDH Advisory information is also available via the web at http://www.vdh.virginia.gov/Epidemiology/PublicHealthToxicology/Advisories/.

9-SNC000.20- 2004 fish tissue finds with application of the new WQS TV for PCB (20 ppb) the addition of 3 species exceeding the new TV criterion. Rock Bass (size 16-20 cm) at 25.21, SM Bass (size 28.6-30.5 cm) at 22.13 and White sucker (1 fish) at 30.08 ppb. Stony Creek is therefore a 2010 addition based on the new WQS PCB tissue value of 20 ppb.

PCB in Fish Tissue - To	e:			River (Miles) 15.22		
New River, Claytor Lake, Peak Creek, Reed Creek and Stony DCR Watershed: N29*	Estua (Sq. Mil		Reservoir (Acres)			
VAW-N29R_NEW04A02 / New River / New River mainstem from the Celeanse Acetate Plant outfalls upstream to the watershed boundary at the confluence of Stony Creek.	5A	PCB in Fish Tissue		2002	2014	5.72
VAW-N29R_NEW03A02 / New River / New River mainstem from the confluence of Wolf Creek upstream to the Celanese Acetate Plant outfalls.	5A	PCB in Fish Tissue		2002	2014	2.79
VAW-N29R_NEW02A02 / New River / New River mainstem from the mouth of Rich Creek upstream to the confluence of Wolf Creek.	5A	PCB in Fish Tissue		2002	2014	3.52
VAW-N29R_NEW01A02 / New River / New River mainstem from the backwaters of Bluestone Reservoir, Route 460, to the confluence of Rich Creek.	5A	PCB in Fish Tissue		2002	2014	3.19
Assessment Unit / Water Name / Description	Caus	e Category / Name	Nested	Cycle First Listed	EPA	Size



## 2010 Impaired Waters

## Categories 4 and 5 by DCR Watershed\*

#### New River Basin

Fact Sheet prepared for DCR Watershed: N29\*


Sources:

Source Unknown

\*Header Information: Location, City/County, Cause/VA Category and Narratives; describe the entire extent of the Impairment. Sizes presented are for Assessment Units (AUs) lying within the DCR Watershed boundary noted above.

## STATE WATER CONTROL BOARD

# NEW RIVER BASIN



## COMPREHENSIVE WATER RESOURCES PLAN

VOLUME V-A
Part 2 of 3

RIVER BASIN WATER QUALITY MANAGEMENT PLAN Planning Bulletin 205A

1976

VSWCB/PB/Q9/W-76/2

- 1. Incorporation of the community and implementation of the plan by the Town.
- 2. Formation of a board or authority to implement the plan.
- Implementation of the plan by the Giles County Public Service Authority.

The Giles County Public Service Authority is the recommended implementing body. The authority would install, maintain, and operate the proposed system. A block diagram of the proposed facility is presented in Plate 65 and the sewer plan layout is presented in Plate 66.

Future Improvements. No future improvements will be needed if the selected alternative is implemented.

Receiving Stream Segment Classification. Sinking Creek is classified as follows:

Past Classification

Effluent Limitation

New Classification

Effluent

(Tables 13 & 148)

(1974 through 1980)

Effluent Limitation

(1980 through 2020)

## Pembroke Planning Area

Planning Area Description. (See Plate 12) The Pembroke Planning Area includes the Town of Pembroke and the area extending east of Pembroke along U. S. Route 460 to Hoges Chapel and north of the corporate limits along Virginia Route 623. The present population of 1,485 is projected to increase to 2,000 by 2020 (Table 28).

Existing Systems. Pembroke is presently served by septic tank-field line systems and cesspools. There are no existing central sewer facilities in the planning area.

Water Quality Problems. Stream assimilation modeling indicates that there are no BOD related water quality problems within the planning area (see Plate A-1, Appendix A).

The presence of sewage from improperly operating septic tankdrain field systems has created a situation which may be potentially
dangerous to public health. It is doubtful that the existing systems
that are functioning adequately can continue to do so throughout the
study period. A more detailed study, such as the 201 Plan, is needed
to evaluate the effect of septic tank systems on groundwater and surface
water.

Degree of Treatment Required. Table 58 indicates that the maximum effluent BOD load for the Pembroke Planning Area is 62.5-pounds per day. Based on this effluent limit and the sanitary raw wasteloads projected in Chapter III, a treatment level of 87.5 percent BOD removal will be required in 2020.

The minimum treatment level required by the Virginia State Water Control Board is secondary treatment or 87.5 percent BOD removal. This level of treatment will be satisfactory through 2020.

Alternative Solutions. Based on per capita flows of 100 gallons per day in 2020, the design flow for the Pembroke Planning Area is

0.157 million gallons per day for 1974 and 0.350 million gallons per day in 2020. The BOD loading ranges from 303 pounds per day in 1974 to 500 pounds per day in 2020 (Table 58).

The "Logic Diagram for Determination of Selected Alternatives" described in Chapter IV and illustrated on Plate 11-A indicates that Route "C" should be used for further analysis of this planning area.

The following alternatives were considered for resolving water quality problems in the area:

Alternative 1. (M/R Plan Solution) Construction of a collection system and a 0.275 million gallon per day sewage treatment plant is recommended. This is the measure recommended by the New River Valley Water Quality Management Plan.

Alternative 2. Retention of the septic tank-field line systems.

Review and Testing of Alternatives. Alternative 1, construction of a sewage treatment plant has been evaluated in terms of cost-effectiveness and environmental impact.

Alternative 2, retention of the existing system, would not solve the potential health problem and would be counter to requirements of water quality control, therefore, its cost has not been included.

A cost estimate for Alternative 1 is presented in Table 217. Total project cost is \$1,857,330, while monthly user cost is \$8.20 per connection. Total present worth is \$2,226,238.

The environmental score for this alternative is +1804 and is tabulated in Table 218. A detailed discussion of the scoring system is presented in Appendix C.

The proposed system could be implemented by the Town or the Giles County Public Service Authority.

Selected Plan. The selected plan for the Pembroke area is Alternative 1: construction of a 275,000 gallon per day sewage treatment plant and collection system which will serve residents inside the corporate limits of the Town of Pembroke, the area east of Pembroke to Hoges Chapel, and the area along Virginia Route 623, north of town. A cost estimate for the selected alternative is given in Table 217. The system will initially serve approximately 400 connections at a monthly cost per connection of \$8.20. Total project cost for the facility is \$1,857, 330.

The treatment plant will be capable of removing 87.5 percent BOD.

Initial flows should average 140,000 gallons per day. Wastewater effluent having an initial BOD loading of 35 pounds per day will be discharged into New River near rivermile 27.0. A block diagram of the proposed facilities is shown in Plate 67.

Implementation by the Town of Pembroke is recommended. A map showing proposed improvements is presented in Plate 68.

Future Improvements. Future extensions to this system are planned along Virginia Route 626, south of town, by 1990. The proposed 1990

extensions will serve an additional 35 connections at a total project cost of \$140,000. A preliminary cost estimate is presented in Table 219.

Wasteflow projections indicate that an expansion of treatment facilities may be necessary around the year 2000. This expansion would be around 75,000 gallons per day if projections hold true. Further evaluation at a future date when the accuracy of the wasteflow projections can be better determined is recommended.

Receiving Stream Segment Classification. The New River is classified as follows:


Past Classification New Classification (Tables 12 & 147)

Effluent Limitation Effluent Limitation (1974 through 2020)

## Bland Planning Area

Planning Area Description (see Plate 12). The Bland Planning Area includes the community of Bland and the surrounding area. The present population of 495 is projected to increase to 725 by 2020.

Existing Systems. There are no existing sewage treatment facilities in the planning area other than individual septic tank-drain field systems. It is estimated that approximately 90 percent of the population use the septic tank system. There are some areas, however, where sewage is disposed of by direct discharge to the stream or by the use of pit privies.



SOURCE THOMPSON & LITTON, INC.

PLATE No.67

Douglas W. Domenech Secretary of Natural Resources



David A. Johnson Director

## COMMONWEALTH of VIRGINIA

## DEPARTMENT OF CONSERVATION AND RECREATION

Division of Natural Heritage 217 Governor Street Richmond, Virginia 23219-2010 (804) 786-7951

September 13, 2012

Becky France DEQ-BRRO 3019 Peters Creek Road Roanoke, VA 24019

Re: VA0088048, Pembroke WWTP

Dear Ms. France:

The Department of Conservation and Recreation's Division of Natural Heritage (DCR) has searched its Biotics Data System for occurrences of natural heritage resources from the area outlined on the submitted map. Natural heritage resources are defined as the habitat of rare, threatened, or endangered plant and animal species, unique or exemplary natural communities, and significant geologic formations.

According to the information currently in our files, the Candy darter (*Etheostoma osburni*, G3/S1/NL/NL) and Hellbender (*Cryptobranchus alleganiensis*, G3G4/S2S3/NL/NL) have been historically documented in the New River. The Candy darter occurs in the New River drainage of Virginia and the Appalachian Plateaus of West Virginia (Jenkins and Burkhead, 1994). It inhabits rocky, clear, and small to large creeks in unsilted runs and riffles (Burkhead and Jenkins, 1991).

Threats to the habitat of this species include siltation and turbidity (Burkhead and Jenkins, 1991). In addition, the stocking of trout may result in predation of the Candy darter while the spawning sites may be trampled by wading trout fishermen (Burkhead and Jenkins, 1991).

The Hellbender, a large, completely aquatic salamander, prefers larger, clear, and fast-flowing streams of the Mississippi drainage (Martof, et. al, 1980). In Virginia, it is documented from the Holston, Clinch, Powell and New River drainages (Pague, 1991). The Hellbender depends on cool, flowing, well-oxygenated water, and it needs a coarse (rocky) substrate (NatureServe, 2009).

Threats to this species include habitat alteration from impoundments or channelization, and water pollution (Pague, 1991). In agricultural areas, siltation may bury the rocky substrates it requires (NatureServe, 2009). In addition, Hellbenders do not tolerate human recreational use of their habitat (NatureServe, 2009).

DCR supports the use of UV disinfection at this facility to improve water quality.

This project is situated on karst-forming carbonate rock and can be characterized by sinkholes, caves, disappearing streams, and large springs. If such features are encountered during the project, please coordinate with Wil Orndorff (540-553-1235, Wil.Orndorff@dcr.virginia.gov) to document and minimize adverse impacts. Discharge of runoff to sinkholes or sinking streams, filling of sinkholes, and alteration of cave entrances can lead to surface collapse, flooding, erosion and sedimentation, groundwater contamination, and degradation of subterranean habitat for natural heritage resources. If the project involves filling or "improvement" of sinkholes or cave openings, DCR would like detailed location information and copies of the design specifications. In cases where sinkhole improvement is for stormwater discharge, copies of VDOT Form EQ-120 will suffice.

There are no State Natural Area Preserves under DCR's jurisdiction in the project vicinity.

Under a Memorandum of Agreement established between the Virginia Department of Agriculture and Consumer Services (VDACS) and the DCR, DCR represents VDACS in comments regarding potential impacts on state-listed threatened and endangered plant and insect species. The current activity will not affect any documented state-listed plants or insects.

New and updated information is continually added to Biotics. Please contact DCR for an update on this natural heritage information if a significant amount of time passes before it is utilized.

The Virginia Department of Game and Inland Fisheries (VDGIF) maintains a database of wildlife locations, including threatened and endangered species, trout streams, and anadromous fish waters that may contain information not documented in this letter. Their database may be accessed from <a href="http://vafwis.org/fwis/">http://vafwis.org/fwis/</a> or contact Gladys Cason (804-367-0909 or <a href="mailto:Gladys.Cason@dgif.virginia.gov">Gladys.Cason@dgif.virginia.gov</a>).

Should you have any questions or concerns, feel free to contact me at 804-371-2708. Thank you for the opportunity to comment on this project.

Sincerely,

S. Rene' Hypes

Project Review Coordinator

Rem Hy

CC: Wil Orndorff, DCR-Karst

#### Literature Cited

Burkhead, Noel M. and Robert E. Jenkins. 1991. Candy darter. In Virginia's Endangered Species: Proceedings of a Symposium. K. Terwilliger ed. The McDonald and Woodward Publishing Company, Blacksburg, Virginia.

Jenkins, R. E., and N. M. Burkhead. 1994. Freshwater fishes of Virginia. American Fisheries Society, Bethesda, Maryland. xxiii + 1079 pp.

Martof, B.S., W.M. Palmer, J.R. Bailey, and J.R. Harrison III. 1980. Amphibians and reptiles of the Carolinas and Virginia. University of North Carolina Press. Chapel Hill, North Carolina.

NatureServe. 2009. NatureServe Explorer: An online encyclopedia of life [web application]. Version 7.1. NatureServe, Arlington, Virginia. Available http://www.natureserve.org/explorer. (Accessed: April 6, 2010).

Pague, C.A. 1991. Hellbender. In Virginia's Endangered Species: Proceedings of a Symposium. K. Terwilliger ed. The McDonald and Woodward Publishing Company. Blacksburg, Virginia.

Attachment F

**Effluent Data** 

## **Effluent Temperature Data for 90th Percentile Calculation**

Days	Jul-07	Aug-07	Sep-07	Oct-07	Nov-07	Dec-07	Jan-08	Feb-08	Mar-08	Apr-08	May-08	Jun-08
1	21.2	22.1	23.3	19.0	14.9	11.8	10.9	8.9	9.2	13.7	14.1	19.5
2	20.1	21.6	23.1	19.4	14.3	12.0	7.4	8.2	8.7	12.6	15.3	19.8
3	20.9	22.3	23.1	20.2	15.4	12.4	6.2	9.7	9.5	12.4	16.1	19.0
4	22.4	23.1	22.0	20.6	15.1	10.2	7.9	9.7	12.2	12.3	16.0	19.5
5	22.1	23.2	20.8	21.1	14.8	10.3	8.1	10.7	10.6	13.1	15.3	20.1
6	22.4	23.2	22.2	21.4	13.7	8.7	9.4	11.7	9.8	12.9	15.2	21.0
7	21.9	23.4	22.4	21.4	13.7	9.4	9.8	10.4	11.1_	12.5	15.3	21.7
8	22.2	23.6	22.3	21.2	12.4	11.0	10.9	11.3	11.6	13.1	17.1	23.3
9	22.2	23.8	22.6	21.2	13.7	13.0	11.9	11.0	6.6	12.7	16.4	21.9
10	23.0	23.3	23.0	20.8	14.6	13.5	11.8	9.8	9.4	13.7	17.0	22.7
11	22.9	23.7	22.8	19.0	12.2	14.4	11.9	7.7	9.0	13.6	16.9	22.1
12	22.3	23.7	22.3	18.2	13.9	13.3	10.6	8.8	9.5	16.0	15.4	22.1
13	21.8	22.1	21.3	16.8	15.5	14.2	10.9	9.3	9.8	14.2	14.6	22.1
14	21.0	22.2	22.1	16.5	15.5	12.9	9.7	6.5	9.8	13.4	15.0	22.3
15	21.3	21.9	21.8	17.5	14.9	11.8	9.7	7.3	11.7	12.1	16.7	22.2
16	22.3	22.4	19.2	18.1	12.3	11.4	8.3	9.4	11.1	12.5	17.4	20.9
17	22.3	23.1	19.6	19.0	12.3	9.5	7.2	10.1	11.2	12.1	15.9	21.1
18	22.5	23.0	19.7	20.2	12.0	8.1	8.8	12.5	10.5	12.6	16.6	20.0
19	23.2	22.0	19.9	20.8	13.9	10.3	9.3	10.9	12.7	14.2	16.1	19.4
20	23.0	22.8	20.0	19.5	15.4	9.4	9.2	10.8	11.5	13.0	15.3	19.2
21	21.8	22.6	21.3	18.5	15.2	10.2	6.9	9.2	11.5	13.9	16.5	19.9
22	21.2	23.1	21.3	18.0	15.6	10.5	7.9	9.6	11.6	14.7	16.2	20.8
23	21.1	23.3	20.3	19.5	13.9	11.5	9.2	11.1	11.0	15.0	16.1	20.1
24	21.1	24.0	21.8	20.3	14.1	10.0	8.3	9.6	10.5	15.3	16.9	20.0
25	21.0	23.1	21.0	19.4	14.6	10.1	5.9	9.6	10.2	15.8	16.6	20.0
26	21.3	23.5	22.5	18.4	13.6	10.3	7.9	10.6	10.8	16.0	17.1	20.4
27	20.9	23.5	21.7	18.2	13.6	10.3	8.7	9.1	11.6	16.8	18.4	21.3
28	21.6	23.6	21.8	17.2	12.7	11.2	8.5	8.6	12.4	16.6	19.0	21.0
29	22.0	23.5	21.6	15.9	11.5	11.2	9.4	7.9	12.4	14.0	18.5	21.9
30	22.5	23.8	18.8	14.2	11.4	11.3	8.6		10.9	13.3	18.6	21.5
31	21.4	23.4		14.9		11.2	8.6		11.0		19.5	

Data are given as Celsius.

90th percentile

22.5 °C

90th percentile

16.6 °C

(wet season - Jan - May)

Effluent pH (S.U.)

Data Dua	min	
Date Due		max
10-Feb-08	6.27	7.04
10-Mar-08	6.59	7.1
10-Apr-08	6.73	7.41
10-May-08	6.61	7.45
10-Jun-08	6.86	7.63
10-Jul-08	6.84	7.83
10-Aug-08	7.29	7.85
10-Sep-08	6.85	7.63
10-Oct-08	6.63	7.37
10-Nov-08	6.39	7.3
10-Dec-08	6.28	7.73
10-Jan-09	6.35	7.54
10-Feb-09	6.94	7.67
10-Mar-09	6.82	7.48
10-Apr-09	6.7	7.54
10-May-09	7.16	7.8
10-Jun-09	7.26	7.75
10-Jul-09	7.22	7.72
10-Aug-09	7.35	7.85
10-Aug-09	7.08	7.92
10-Sep-09	7.26	7.82
10-Nov-09	6.88	7.59
I		
10-Dec-09	6.92 6.94	7.58
10-Jan-10	•	7.89
10-Feb-10	6.9	7.43
10-Mar-10	7	7.38
10-Apr-10	6.98	7.45
10-May-10	6.94	7.46
10-Jun-10	6.28	7.83
10-Jul-10	7.28	7.72
10-Aug-10	7.23	7.73
10-Sep-10	7.25	7.87
10-Oct-10	7.42	7.84
10-Nov-10	7.17	7.95
10-Dec-10	6.75	7.53
10-Jan-11	6.24	7.35
10-Feb-11	6.46	7.11
10-Mar-11	6.35	7.29
10-Apr-11	6.49	7.13
10-May-11	6.56	7.48
10-Jun-11	7.29	7.8
10-Jul-11	7.53	8.18
10-Aug-11	7.34	7.98
10-Sep-11	7.33	7.9
10-Oct-11	7.35	7.77
10-Nov-11	6.36	7.74
10-Dec-11	6.39	7.39
10-Jan-12	6.04	7.1
10-Feb-12	6.3	7.53
10-Mar-12	6.02	6.73
10-Mai-12	6.22	6.82
10-Api-12	6.18	7.08
10-May-12	6.37	7.08
10-3un-12	6.46	7.07
1		7.36 7.19
10-Aug-12	6.47	
10-Sep-12	6.5	7.2

90th Percentile pH 7.9 S.U. 10th Percentile pH 6.2 S.U.

## Pembroke WWTP VPDES Permit No. VA0088048

## Effluent pH (S.U.)

Date Due	min	max
10-Oct-12	6.19	7.23
10-Nov-12	6.33	7.02
10-Dec-12	6.17	6.63
10-Jan-13	6.06	6.79
10-Feb-13	6.17	7.72
10-Mar-13	6.61	7.56



Pace Analytical Services, Inc. 205 East Meadow Road - Suite A Eden, NC 27288 (338)623-8921 Pace Analytical Services, Inc. 2225 Riverside Dr. Asheville, NC 28804 (828)254-7176 Pace Analytical Services, Inc. 9800 Kincey Ave. Suite 100 Huntersville, NC 28078 (704)875-9092

## **ANALYTICAL RESULTS**

Project:

5 Year Testing

Pace Project No.:

92133832

Sample: WW 1	Lab ID: 92133832001	Collected	10/02/12 09:	00 Received: 1	0/03/12 10:00	Matrix: Water	
		Report					
Parameters	Results Units	Limit	MDL D	F Prepared	Analyzed	CAS No.	Qual
608 GCS Pesticides and PCBs	Analytical Method: EPA 6	608 Preparat	ion Method: El	PA 3535			
4,4'-DDD	ND ug/L	0.050	0.050 1	10/04/12 12:11	1 10/05/12 16:2	7 72-54-8	
4,4'-DDE	ND ug/L	0.050	0.050 1	10/04/12 12:11	1 10/05/12 16:2	7 72-55-9	
4,4'-DDT	ND ug/L	0.050	0.050 1	10/04/12 12:11	1 10/05/12 16:2	7 50-29-3	
Heptachlor epoxide Surrogates	ND ug/L	0.050	0.050 1	10/04/12 12:11	l 10/05/12 16:2	7 1024-57-3	
Tetrachloro-m-xylene (S)	45 %	20-110	1	10/04/12 12:11	1 10/05/12 16:2	7 877-09-8	
Decachlorobiphenyl (S)	153 %	20-138	1	10/04/12 12:11	10/05/12 16:2	7 2051-24-3	S5
Sample: WW 3	Lab ID: 92133832002	Collected	10/02/12 09:	04 Received: 1	0/03/12 10:00	Matrix: Water	
		Report					
Parameters	Results Units	Limit	MDL DI	Prepared	Analyzed	CAS No.	Qual
8270 MSSV Semivolatile Organic	Analytical Method: EPA 8	270 Prepara	ition Method: E	EPA 3510			
Benzidine	ND ug/L	50.0	5.1 1	10/09/12 15:00	0 10/10/12 15:2	5 92-87-5	
bis(2-Chloroethyl) ether	ND ug/L	10.0	1.0 1	10/09/12 15:00	10/10/12 15:2	5 111-44-4	
bis(2-Chloroisopropyl) ether	ND ug/L	10.0	0.95 1	10/09/12 15:00	10/10/12 15:2	5 108-60-1	
2-Chloronaphthalene	ND ug/L	10.0	0.98 1	10/09/12 15:00	10/10/12 15:2	5 91-58-7	
3,3'-Dichlorobenzidine	ND ug/L	20.0	2.1 1	10/09/12 15:00	10/10/12 15:2	5 91-94-1	
Dimethylphthalate	ND ug/L	10.0	0.76 1	10/09/12 15:00	10/10/12 15:2	5 131-11-3	
4,6-Dinitro-2-methylphenol	ND ug/L	20.0	2.6 1	10/09/12 15:00	10/10/12 15:2	5 534-52-1	
2,4-Dinitrophenol	ND ug/L	50.0	9.0 1	10/09/12 15:00	10/10/12 15:2	5 51-28-5	
2,4-Dinitrotoluene	ND ug/L	10.0	0.90 1				
1,2-Diphenylhydrazine	ND ug/L	10.0	0.90 1				
Hexachloro-1,3-butadiene	ND ug/L	10.0	0.94 1				
Hexachlorocyclopentadiene	ND ug/L	10.0	0.88 1				
Hexachloroethane	ND ug/L	10.0	1.1 1				
Indeno(1,2,3-cd)pyrene Kepone	ND ug/L	10.0	0.29 1	,			
N-Nitrosodimethylamine	ND ug/L	10.0	8.3 1				
N-Nitrosodimetriylamine N-Nitrosodiphenylamine	ND ug/L	10.0	0.91 1				
Parathion (Ethyl parathion)	ND ug/L ND ug/L	10.0 10.0	1.0 1 5.1 1		-		
1,2,4-Trichlorobenzene	ND ug/L	10.0	0.98 1				
Surrogates	HU ug/L	10.0	0.50	10/09/12 15:00	) 10/10/12 15:2	∪ 12U-82-1	
Nitrobenzene-d5 (S)	39 %	21-110	1	10/09/12 15:00	10/10/12 15:2	5 4165-60-0	
2-Fluorobiphenyl (S)	36 %	27-110	1				
Terphenyl-d14 (S)	77 %	31-107	1				
Phenol-d6 (S)	11 %	10-110	1	10/09/12 15:00		5 13127-88-3	
2-Fluorophenol (S)	19 %	12-110	1		=		
2,4,6-Tribromophenol (S)	56 %	27-110	1		= :		



## Pace Analytical Services, Inc. 205 East Meadow Road - Suite A Eden, NC 27288 (336)623-8921

Pace Analytical Services, Inc. 2225 Riverside Dr. Asheville, NC 28804 (828)254-7176 Pace Analytical Services, Inc. 9800 Kincey Ave. Suite 100 Huntersville, NC 26078 (704)875-9092

## **ANALYTICAL RESULTS**

Project:

5 Year Testing

Pace Project No.:

92133832

Sample: WW 4	Lab ID:	92133832003	Collected:	10/02/1	2 09:06	Received: 10/	/03/12 10:00 N	latrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
7196 Chromium, Hexavalent Diss	Analytica	Method: EPA 7	196						
Chromium, Hexavalent, Dissolved	<b>N</b> D n	ng/L	0.050	0.050	1		10/04/12 22:27	18540-29-9	нз
Sample: WW 5	Lab ID:	92133832004	Collected:	10/02/1	2 09:08	Received: 10/	/03/12 10:00 M	atrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
6010 MET ICP, Dissolved	Analytical	Method: EPA 6	010 Prepara	tion Meth	od: EPA	3010			•
Chromium, Dissolved Thallium, Dissolved	ND u ND u	•	5.0 10.0	0.40 3.0	1 1	10/06/12 18:15 10/06/12 18:15	10/09/12 01:33 10/09/12 01:33		
Sample: WW 6	Lab ID:	92133832005	Collected:	10/02/12	2 09:10	Received: 10/	03/12 10:00 M	atrix: Water	
Parameters	Results	Units	Report Limit	MDL	DF	Prepared	Analyzed	CAS No.	Qual
624 Volatile Organics	Anabaisas								
10.00.0 Olganico	Analytical	Method: EPA 6	24						
•	. Analytical ND u		24 100	8.8	1		10/06/12 06:36	107-02-8	
Acrolein		g/L		8.8 11.5	1		10/06/12 06:36 10/06/12 06:36		
Acrolein Acrylonitrile	ND u	g/L g/L	100					107-13-1	
Acrolein Acrylonitrile Bromomethane	ND u	g/L g/L g/L	100 100	11.5	1		10/06/12 06:36	107-13-1 74-83-9	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane	ND u ND u ND u	g/L g/L g/L g/L	100 100 10.0	11.5 2.5	1		10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene	ND u ND u ND u ND u ND u	g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6	1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene	ND U ND U ND U ND U ND U ND U	g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6 1.6	1 1 1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5 10061-01-5	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene 1,1,2,2-Tetrachloroethane	ND U ND U ND U ND U ND U ND U ND U	g/L g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6 1.6 1.5	1 1 1 1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5 10061-01-5 10061-02-6	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane	ND U ND U ND U ND U ND U ND U	g/L g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6 1.6	1 1 1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5 10061-01-5 10061-02-6 79-34-5	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane Surrogates	ND U ND U ND U ND U ND U ND U ND U	g/L g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6 1.6 1.5	1 1 1 1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5 10061-01-5 10061-02-6 79-34-5 79-00-5	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane Surrogates Dibromofluoromethane (S)	ND U ND U ND U ND U ND U ND U ND U ND U	g/L g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6 1.6 1.5	1 1 1 1 1 1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5 10061-01-5 10061-02-6 79-34-5 79-00-5	
Acrolein Acrylonitrile Bromomethane trans-1,2-Dichloroethene 1,2-Dichloropropane cis-1,3-Dichloropropene trans-1,3-Dichloropropene 1,1,2,2-Tetrachloroethane 1,1,2-Trichloroethane Surrogates	ND U ND U ND U ND U ND U ND U ND U	g/L g/L g/L g/L g/L g/L g/L g/L	100 100 10.0 5.0 5.0 5.0 5.0 5.0	11.5 2.5 1.8 1.7 1.6 1.6 1.5	1 1 1 1 1 1		10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36 10/06/12 06:36	107-13-1 74-83-9 156-60-5 78-87-5 10061-01-5 10061-02-6 79-34-5 79-00-5 1868-53-7 460-00-4	



Pace Analytical Services, Inc. 205 East Meadow Road - Suite A Eden, NC 27288 (336)623-8921

Pace Analytical Services, Inc. 2225 Riverside Dr. Asheville, NC 28804 (828)254-7176 Pace Analytical Services, Inc. 9800 Kincey Ave. Suite 100 Huntersville, NC 28078 (704)875-9092

#### **QUALIFIERS**

Project:

5 Year Testing

Pace Project No.:

92133832

#### **DEFINITIONS**

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to changes in sample preparation, dilution of the sample aliquot, or moisture content.

ND - Not Detected at or above adjusted reporting limit.

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PRL - Pace Reporting Limit.

RL - Reporting Limit.

S - Surrogate

1,2-Diphenylhydrazine (8270 listed analyte) decomposes to Azobenzene.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Acid preservation may not be appropriate for 2-Chloroethylvinyl ether, Styrene, and Vinyl chloride.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

#### **LABORATORIES**

PASI-A Pace Analytical Services - Asheville
PASI-C Pace Analytical Services - Charlotte

### **ANALYTE QUALIFIERS**

Н3	Sample was received or analysis requested beyond the recognized method holding time.
L2	Analyte recovery in the laboratory control sample (LCS) was below QC limits. Results for this analyte in associated samples may be biased low.
MO	Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
М3	Matrix spike recovery was outside laboratory control limits due to matrix interferences.
R1	RPD value was outside control limits.
S3	Surrogate recovery exceeded laboratory control limits. Analyte presence below reporting limits in associated samples. Results unaffected by high bias.
S5	Surrogate recovery outside control limits due to matrix interferences (not confirmed by re-analysis)

## **ANALYTICAL DATA REPORT**

UL ORDER ID 1210089

UL Sample Number 1210089-001

10/2/2012 09:02:00

Sample Site: <u>WW2 92133832006</u>

Grab Date/Time: Composite Start:

N/A

Client Sample ID: WW2 92133832006

Composite Stop: N/A

N/A

Sample Matrix: Wastewater

Collected By: CLIENT

Test Result

RL Analysis Date/Time

Parameter GC/FPD

GC/FPD
TBT Tributyltin

< 0.03

Units

ug/L

0.03

10/12/2012 14:43:00

HAM

**Location Comment** 

Comments for 1210089-001

No comments

TOLL-FREE: (800) 695-2162 TELEPHONE: (757) 865-0880

## **ANALYTICAL DATA REPORT**

NCDW Lab # 51706 (Hampton) VELAP ID 460036 (Hampton)

## UL ORDER ID 1210089

**Analytical Methods Reference** 

VDEH Lab# 00030 (Hampton)

VDEH Lab# 00065 (Fredericksburg) NCWW Lab # 543 (Hampton)

VELAP ID 460164 (Fredericksburg

Description:

Prep Method:

Reference

accredited/status

**Wastewater** 

TBT Tributyitin

liq/liq

GC/FPD

Method

Accredited

NOTE: Analysis is performed according to Universal Laboratories Standard Operating Procedures which are based on the analytical methods referenced above

## **GLOSSARY OF TERMS AND ABBREVIATIONS**

RL (Reporting Limit): The minimum levels, concentrations, or quantities of target analyte that can be reported with a specified degrees of confidence. Generally this number is near or equal to the lowest calibration standard run with the analytical batch.

MDL (Method Detection Limit): The constituent concentration that, when processed through the complete method, produces a signal with a 99% probability that it is different from the blank.

LCS (Laboratory Control Sample): is a sample matrix free from the analytes of interest, spiked with verified amounts of analytes.

MS (Matrix Spike): a sample prepared by adding a known mass of target analyte to a specific amount of sample for which an independant estimate of target analyte concentration is available.

MSD (Matrix Spike Duplicate); is a replicate matrix spike prepared in the laboratory and anlyzed to obtain a measure of the precision recovery for each analtye.

Surrogate is a substance with properties that mimic the analyte of interest. It is unlikely to be found in environmental samples and is added to them for quality control purposes

IS (Internal Standard): is a known amount of standard added to a test portion of the sample as a reference for evaluation and controlling the precsion and bias of the applied analytical method, RPD (Relative Percent Difference) is the difference between a set of sample duplicates or sample spike duplicates

ICV (Initial Calibration Verification) CCV (Continuing Calibration Verification) FCV (Final Calibration Verification)

Method Blank is a sample matrix smiler to the batch of associated samples that is free from analytes of interest and is processed simultaneously with and under the same conditions as samples.

Trip Blank is a sample of analyte free media collected in the same type of container that is required for the analytical test, taken from the laboratory to the sampling site and returned to the laboratory unopened. A trip blank is used to document contamination attributable to shipping and field handling procedures

Holding Time is the maximum times that samples may be held prior to analysis and still be considered valid or not compromised

ug/L=ppb ug/kg≃ppb

mg/kg=ppm mg/L=ppm

HAM= Analyzed in Hampton Lab

FRED= Analyzed in Fredericksburg Lab

QC Flag	Description
В	Analyte found in method blank
H	Holding time exceeded
L	LCS outside acceptable limits
>	ICV/CCV/FCV outside acceptable limits
D	RPD outside acceptable limits
MS	Matrix spike recovery outside acceptable limits
J	Result above calibration curve approximate value
QC	Method QC Critera not met
MI	Matrix Interference
S	Surrogate outside acceptable limits
	Internal standard outside acceptable limits

TOLL-FREE: (800) 695-2162 TELEPHONE: (757) 865-0880 REI Consultants, Inc.

**Analytical Results** 

Date: 25-Jun-08

CLIENT:

TOWN OF PEMBROKE

Client Sample ID: 001 GRAB

Project:

ATTACHEMENT A

Site ID:

VA 0088048

WorkOrder: 0704252

Lab ID:

0704252-01A

Collection Date: 4/4/2007 10:00:00 AM

Matrix:

WASTE WATER

Analyses	Result Units	Qual	PQL	MCL	Prep Date	Date Analyzed
DISSOLVED METALS BY ICP-MS		E200.8			Analyst: DBB	
Antimony	ND mg/L		0.0010	NA	04/09/07 12:00 AM	04/10/07 11:35 AM
SEMIVOLATILE ORGANIC COMPOUN	DS	E625			Analyst: CLS	
Acenaphthene	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
Butyl benzyl phthalate	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
2-Chlorophenol	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
Di-n-butyi phthalate	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
2,4-Dichlorophenol	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
Diethyl phthalate	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
2,4-Dimethylphenol	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
Fluorene	ND mg/L -		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
Nitrobenzene	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
1,2,4-Trichlorobenzene	ND mg/L		0.0104	NA	04/11/07 11:02 AM	04/12/07 8:06 PM
VOLATILE ORGANIC COMPOUNDS		SW8021B			Analyst: M	
m.p-Xylene	ND µg/L		2.00 -	NA	<del></del>	- 04/09/07 4:55 PM
o-Xylene	ND μg/L		1.00	NΑ	•	04/09/07 4:55 PM
VOLATILE ORGANIC COMPOUNDS		E624			Analyst: AS	
1,1-Dichlorœthene	ND µg/L		5.0	NA	·	04/09/07 11:37 AM
HYDROGEN SULFIDE		E376.1			Analyst: <b>LK</b>	
Hydrogen Sulfide	1.40 mg/L	•	1.00	NA		04/06/07 3:00 PM

- Key:	_MCL_	Maximum Contaminant Level Qualifiers:	В	Analyte detected in the associated Method Blank
_	MDL	Minimum Detection Limit	E	Estimated Value above quantitation range
	NA	Not Applicable	H	Holding times for preparation or analysis exceeded
	ND	Not Detected at the PQL or MDL	S	Spike/Surrogate Recovery outside accepted recovery limits
	PQL	Practical Quantitation Limit	*	Value exceeds Maximum Contaminant Level Page 2 of 3
	TIC	Tentatively Identified Compound, Estimated Concentration		Thinker.

REI Consultants, Inc.

**Analytical Results** 

Date: 25-Jun-08

CLIENT:

TOWN OF PEMBROKE

Client Sample ID: 001 COMP

Project:

ATTACHEMENT A

Site ID:

VA 0088048

WorkOrder:

0704252

Lab ID:

0704252-02A

Collection Date: 4/4/2007 10:00:00 AM

Matrix:

WASTE WATER

Analyses	Result Units	Qual	PQL	MCL	Prep Date	Date Analyzed
HARDNESS		SM2340 B			Analyst: JI	
Hardness, Total (As CaCO3)	53.8 mg/L		1.00	NA	04/09/07 12:00	AM 04/09/07 10:27 PM

Key:	-MCL-	-Maximum Contaminant Level	Qualifiers:B	Analyte detected in the associated introd Blank
	MDL	Minimum Detection Limit	E	Estimated Value above quantitation range
	NA	Not Applicable	H	Holding times for preparation or analysis exceeded
	ND	Not Detected at the PQL or MDL	, 8	Spike/Surrogate Recovery outside accepted recovery limits
	POL	Practical Quantitation Limit	*	Value exceeds Maximum Contaminant Level Page 3 of 3



14806

DEO - WORd

Client Date Town of Pembroke September 6, 2002

001 10 2m2

Sample No.:

149872

n Na fire arts ets an account

**Date Collected:** 

8/21/02

Time Collected:

9:30 a.m.

Description:

Effluent Wastewater

Grab

<u>Analysis</u> Total Cyanide (EPA 335.2)	<u>Re</u> BQL	s <u>ult</u>	100	<u> Դ</u> աց/L	SST N/A	<u>-v</u>	Date/Time <u>Analyzed</u> 8/22/02; 0800	Analysts' <u>Initials</u> SBH
Dissolved Hexavalent (SM 3500Cr,D) Total Arsenic (EPA 200.9) Total Barium (EPA 200.7) Total Cadmium (EPA 200.9) Total Copper (EPA 200.9) Total Lead (EPA 200.9) Total Mercury (EPA 245.1) Total Nickel (EPA 200.9) Total Selenium (EPA 200.9) Total Silver (EPA 200.9) Total Zinc (EPA 200.7)	BQL BQL BQL 12 BQL BQL BQL BQL 89	μg/L μg/L	50 10 20 1 10 10 0.2 10 10 2 50	μg/L μg/L μg/L μg/L μg/L μg/L μg/L μg/L	384 50 N/A 65 312 1,884 16 3,327 480 55 2,130	μg/L μg/L μg/L μg/L μg/L μg/L μg/L μg/L	8/21/02; 1130 8/26/02; 1820 8/28/02; 1045 8/28/02; 0830 8/28/02; 1720 8/26/02; 1400 8/26/02; 1200 8/26/02; 1900 8/26/02; 2200 8/28/02; 1315 8/28/02; 1045	NA TSS SC TSS TSS SAH TSS TSS TSS SC

SSTV = Site-Specific Target Value BQL = Below Quantitation Limit N/A = Not Applicable

## OLVER

Client Sheet No.

14806

Client Date Town of Pembroke September 6, 2002

Sample No.:

149873

Date Collected:

8/20/02

Time Collected:

8:00 a.m.

Description:

Effluent Wastewater

Grab

DEO: WORD

7 4 0 000

RECEIVED

	•			Date/Time	Analyst
<u>Analysis</u>	Result		<u>QL</u>	<u>Analyzed</u>	<u>Initials</u>
Pesticides/PCBs (EPA 608):		•	<del>_</del>	8/29/02; 0855	, DŁ
Aldrin	BQL	0.05	μg/L		
Chlordane	BQL	0.2	μg/L		-
DDT	BQL	0.1	μg/L		
Dieldrin	BQL	0.1	μg/L		
Endosulfan I	BQL	0.1	μg/L		
Endosulfan II	BQL	0.1	μg/L		
Endosulfan Sulfate	BQL	0.1	μg/L		
Endrin	BQL.	0.1	μg/L		4,
Heptachlor	BQL	0.05	μg/L	:	•
Hexachlorocyclohexane	BQL	0.05	μg/L		
Methoxychior	BQL	- 10	μg/L		
Mirex	BQL	0.1	μg/L		
Toxaphene	BQL	5.0	μg/L	•	
PCB-1242	BQL	1.0	μg/L	,	•
PCB-1254	BQL	1.0	μg/L		-
PCB-1221	BQL	1.0	μg/L		
PCB-1232	BQL	- 1.0	μg/L		ě,
PCB-1248	BQL	1.0	μg/L		
PCB-1260	BQL	1.0	μg/L		
PCB-1016	BQL	1.0	μ <b>g/L</b>		

14806

Client

Town of Pembroke September 6, 2002

Date

Sample No.:

149873

**Date Collected:** 

8/20/02

Time Collected:

8:00 a.m.

Description:

Effluent Wastewater

Grab

<u>Analysis</u> Pesticides (EPA 622):	Result		<u>QL</u>	Date/Time <u>Analyzed</u> 8/29/02; 0855
	BQL	0.2	μg/L	·
Chlorpyrifos (Dursban) Demeton	BQL	0.2	μg/L	•
	BQL	0.2	μg/L	
Guthion	BQL	0.2	µg/∟ µg/L	
Malathioπ	BQL	0.2		·
Parathion (2014) 242 2454A	DUL	0.2	μg/L	8/30/02; 1526
Herbicides (SW-846 8151A):	BQL	0.2	uedl	0/00/02, 1020
2,4,5-Trichlorophenoxypropionic acid (Silvex)	BQL	0.2	μg/L	
2,4-Dichlorophenoxy (2,4-D)		0.2	μg/L	8/20/02; 2149
Base/Neutral Extractable Organic Compounds (E	PA 020).	10	!	0/20/02, 2143
Anthracene	BQL		μg/L	
Benzo(a)anthracene	BQL		μg/L	
Benzo(b)fluoranthene	BQL	10	μg/L	
Benzo(k)fluoranthene	BQL	10	μg/L	•
Benzo(a)pyrene	BQL	10	μg/L "	·
Chrysene	BQL	10	μg/L	
Dibenz(a,h)anthracene	BQL	20	μg/L	
1,2-Dichlorobenzene	BQL -	10	μg/L	
1,3-Dichlorobenzene	BQL	10	μg/L	
1,4-Dichlorobenzene	BQL	10	μg/L	
2,4-Dinitrotoluene	BQL	10	μg/L	•
Di-2-ethylhexylphthalate	BQL	10	μg/L	
Fluoranthene	BQL	10	μg/L	
Indeno (1,2,3-cd) Pyrene	BQL	20	μg/L	•
Isophorone	BQL	10	μg/L	
Naphthalene	BQL	10	μg/L	
Pyrene	BQL	10	μg/L	

Analyst <u>Initials</u>

PMW

DF

**PMW** 





14806

Client

Town of Pembroke September 6, 2002

Date

149873

**Date Collected:** 

Sample No.:

8/20/02

Time Collected:

8:00 a.m.

Description:

Effluent Wastewater

Grab

Util - Want

OF 1 1 122

RECEWED

Analysis	Result	<u>QL</u>	Date/Time <u>Analyzed</u>	Analyst <u>Initials</u>
Acid Extractables Organic Compounds (EPA	625):		8/28/02; 2149	PMW
Pentachlorophenol	BQL	50 μg/L		
Phenol	BQL	10 μg/L	÷	
2,4,6-Trichlorophenol	BQL	10 μg/L		
Volatile Organic Compounds (EPA 624):	•		8/23/02; 0615	BP
Benzene	BQL	10 μg/L		
Bromoform	BQL	10 μg/L		
Carbon Tetrachloride	BQL	10 μg/L		
Chlorodibromomethane	BQL	10 μg/L		
Chloroform	BQL	10 μg/L		
Chloromethane	BQL	20 μg/L		
Dichloromethane	BQL.	10 μg/L		
Dichlorobromomethane	BQL	20 μg/L	-	
1,2-Dichloroethane	BQL	10 μg/L		_
Ethylbenzene	BQL	10 μg/L		
Monochlorobenzene	BQL ,	50 μg/L		
Tetrachloroethylene	BQL ~	10 μg/L		``
Toluene	BQL	10 μg/L		•
Trichloroethylene	BQL	10 μg/L	•	
Vinyl chloride	BQL <sup>.</sup>	10 μg/L	·	



Client Date 14806

Town of Pembroke September 6, 2002

DEG - WEEDO

Sample No.:

149874

Date Collected:

8/20/02

Time Collected:

4:00 p.m.

Description:

Effluent Wastewater

Grab

PECEIVED	÷
·	

<u>Analysis</u>	Result	<u>QL</u>	Date/Time Analyst Analyzed Initials 8/29/02; 1029 PMW
Pesticides/PCBs (EPA 608):		0.05 (	6/29/02, 1029
Aldrin	BQL	0.05 μg/L	
Chlordane	BQL	0.2 μg/L	
DDT	BQL	0.1 μg/L	
Dieldrin	BQL	0.1 μg/L	
Endosulfan I	BQL	0.1 μg/L	
Endosulfan II	BQL	0.1 μg/L	
Endosulfan Sulfate	BQL	0.1 μg/L	•
Endrín	BQL	0.1 μg/L	
Heptachlor	BQL	0.05 μg/L	•
Hexachlorocyclohexane	BQL .	0.05 μg/L	•
Methoxychlor	BQL	10 μg/L	•
Mirex	BQL	0.1 μg/L	
Toxaphene	BQL	5.0 μg/L	
PCB-1242	BQL -	1.0 μg/L	
PCB-1254	BQL	1.0 μg/L	•
PCB-1221	BQL	1.0 μg/L	
PCB-1232	BQL	1.0 μg/L	
PCB-1248	BQL	1.0 μg/L	
PCB-1260	BQL	1.0 μg/L	
PCB-1016	BQL	1.0 μg/L	·

## OLVER LABORATORIES

Client Sheet No.

14806

Client Date Town of Pembroke September 6, 2002

Sample No.:

149874

Date Collected:

8/20/02 --

Time Collected:

4:00 p.m.

Description:

Effluent Wastewater

Grab

DEG-WCPO

001 16 502

RECEIVED

Analysis Pesticides (EPA 622):	<u>Result</u> .		<u>QL</u>	Date/Time <u>Analyzed</u> 8/29/02; 0926	Analyst <u>Initials</u> DF
Chlorpyrifos (Dursban)	BQL	0.2	μg/L	,	••
Demeton	BQL	0.2	μg/L		
	BQL	0.2	μg/L		
Guthion	BQL	0.2	μg/L μg/L	•	
Malathion	BQL	0.2	μg/L	•	
Parathion	DQL .	0.2	μ <del>9</del> , <b>–</b>	8/30/02; 1542	DF
Herbicides (SW-846 8151A): 2,4,5-Trichlorophenoxypropionic acid (Silvex)	BQL	0.2	μg/L	• · · • · · · · · · · · · · · · · · · ·	
	BQL	0.2	μg/L		
2,4-Dichlorophenoxy (2,4-D)  Base/Neutral Extractable Organic Compounds (E		0.2	µ9/ с	8/28/02; 1029	PMW
	BQL	10	μg/L	<b>3.23.32</b> , 1323	
Anthracene	BQL	. 10	μg/L μg/L		
Benzo(a)anthracene	BQL	10	μg/L μg/L		
Benzo(b)fluoranthene	BQL	10	μg/L μg/L		
Benzo(k)fluoranthene	BQL	10	μg/L μg/L	•	
Benzo(a)pyrene	BQL	10	μg/L μg/L	•	•
Chrysene	BQL -	20	μg/L μg/L		
Dibenz(a,h)anthracene	BQL -	10	μg/L μg/L		i,
1,2-Dichlorobenzene	BQL	10			
1,3-Dichlorobenzene	BQL	10	μg/L		
1,4-Dichlorobenzene	BQL	10	μg/L		
2,4-Dinitrotoluene			μg/L		
Di-2-ethylhexylphthalate	BQL	10	μg/L		
Fluoranthene	BQL	10	μg/L		
Indeno (1,2,3-cd) Pyrene	BQL	20	μg/L - "		
Isophorone	BQL	10	μg/L		
Naphthalene	BQL	10	μg/L		
Pyrene	BQL	10	μg/L		

## **OLVER**LABORATORIES

Client Sheet No.

Sample No.:

14806

Client

Town of Pembroke September 6, 2002

Date

•

149874

Date Collected:

8/20/02

Time Collected:

4:00 p.m.

Description:

Effluent Wastewater

Grab

RECEIVED

Analysis Acid Extractables Organic Compounds (EPA 625	<u>Result</u>		<u>QL</u>	Date/Time Analyst Analyzed Initials 8/28/02; 1029 PMW
Pentachlorophenol	BQL	50	μg/L	, and the second se
Phenol	BQL	10	μg/L	
2,4,6-Trichlorophenol	BQL	10	μg/L	
Volatile Organic Compounds (EPA 624):	•			8/23/02; 0644 BP
Benzene	BQL	10	μg/L	
Bromoform	BQL	10	μg/L	•
Carbon Tetrachloride	BQL	10	μg/L	
Chlorodibromomethane	BQL	10	μ <b>g</b> /L	
Chloroform	BQL	10	μg/L	
Chloromethane	BQL	20	μg/L	
Dichloromethane	BQL	10	μg/L	
Dichlorobromomethane	BQL	20	μg/L	•
1,2-Dichloroethane	BQL	10	μg/L	
Ethylbenzene	BQL	10	μg/L	
Monochlorobenzene	BQL	50	μg/L	,
Tetrachloroethylene	BQL ~	10	μg/L	· ·
Toluene	BQL	10	μg/L	•
Trichloroethylene	BQL	10	μg/L	'
Vinyl chloride	BQL	10	μg/L	

14806

Client

Town of Pembroke

Date

September 6, 2002

Sample No.:

149875

Date Collected:

8/21/02

Time Collected:

12:00 a.m.

Description:

Effluent Wastewater

Grab

Analysis	Result	<u>0</u>	ĎΓ	Date/Time <u>Analyzed</u> 8/29/02; 0956	Analyst <u>Initials</u> DF
Pesticides/PCBs (EPA 608):	BQL	0.05	μg/L	•	
Aldrin	BQL	0.2	μg/L		
Chlordane	BQL	0.1	μg/L μg/L		
DDT		0.1			
Dieldrin	BQL	0.1	μg/L α/l	•	
Endosulfan I	BQL		μg/L		
Endosulfan II	BQL	0.1	μg/L		
Endosulfan Sulfate	BQL	0.1	μg/L		•
Endrin	BQL	0.1	μg/L		
Heptachlor	BQL	~ 0.05	μg/L		
Hexachlorocyclohexane	BQL	0.05	μg/L		
Methoxychlor	BQL	10	μg/L	•	
Mirex	BQL	0.1	μg/L		
Toxaphene	BQL	5.0	μg/L		
PCB-1242	BQL	_ 1.0	μg/L		· 🔥
PCB-1254	BQL	<sup>-</sup> 1.0	μg/L		**
PCB-1221	BQL	1.0	μg/L		
PCB-1232	BQL	1.0	μg/L		
PCB-1248	BQL.	1.0	μg/L		
PCB-1260	BQL	1.0	μg/L		
PCB-1016	BQL	1.0	μg/L		
, 02					

tien-were

RECEIVED .





14806

Client Date Town of Pembroke

September 6, 2002

BEO - WORD

ECT 16 212

RECEIVED

Sample No.:

149875

**Date Collected:** 

8/21/02

Time Collected:

12:00 a.m.

Description:

Effluent Wastewater

Grab

			01	Date/Time	Analyst
Analysis	<u>Result</u>		<u>QL</u>	Analyzed	<u>Initials</u>
Pesticides (EPA 622):				8/29/02; 0956	PMW
Chlorpyrifos (Dursban)	BQL	0.2	μg/L		
Demeton	BQL	0.2	μg/L		
Guthion	BQL	0.2	μg/L		
Malathion	BQL	0.2	μg/Ľ		
Parathion	BQL	0.2	μg/L		
Herbicides (SW-846 8151A):				8/30/02; 1557	DF
2,4,5-Trichlorophenoxypropionic acid (Silvex)	BQL	0.2	μg/L		
2,4-Dichlorophenoxy (2,4-D)	BQL	0.2	μg/L		
Base/Neutral Extractable Organic Compounds (E	PA 625):			8/29/02; 0112	PMW
Anthracene	BQL	10	μg/L	•	
Benzo(a)anthracene	BQL	10	μg/L		
Benzo(b)fluoranthene	BQL	10	μg/L		
Benzo(k)fluoranthene	BQL	10	μg/L	•	
Benzo(a)pyrene	BQL	10	μg/L	:	
Chrysene	BQL	10	μg/L		
Dibenz(a,h)anthracene	BQL .	20	μg/L		ξ,
1,2-Dichlorobenzene	BQL	10	μg/L		**
1,3-Dichlorobenzene	BQL	10	μg/L		
1,4-Dichlorobenzene	BQL	10	μg/L		
2,4-Dinitrotoluene	BQL	10	μg/L	•	
Di-2-ethylhexylphthalate	BQL	10	μg/L		
Fluoranthene	BQL	10	μg/L		
Indeno (1,2,3-cd) Pyrene	BQL	20	μg/L		
Isophorone	BQL	10	μg/L		
Naphthalene	BQL	10	μg/L		
Pyrene	BQL	10	μg/L	•	





14806

Client Date

Town of Pembroke September 6, 2002

. DEO - WCBO

Sample No.:

149875

**Date Collected:** 

8/21/02

Time Collected:

12:00 a.m.

Description:

Effluent Wastewater

Grab

007 76 202

RECEIVED

<u>Analysis</u>	Result		<u>QL</u>	Date/Time <u>Analyzed</u>	Analyst <u>Initials</u>
Acid Extractables Organic Compounds (EP				8/29/02; 0112	``PMW
Pentachlorophenol	BQL	50	μg/L		,
Phenol	BQL	10	μg/L	•	
2,4,6-Trichlorophenol	BQL	10	μg/L -		
Volatile Organic Compounds (EPA 624):	•			8/23/02; 0713	BP
Benzene	BQL	10	μg/L		
Bromoform	BQL	10	μ <b>g/L</b>	v	
Carbon Tetrachloride	BQL	10	μ <b>g/L</b>		•
Chlorodibromomethane	BQL	10	μg/L		
Chloroform	BQL	10	μg/L ·		
Chloromethane	BQL	20	μg/L		
Dichloromethane	BQL	10	μg/L		
Dichlorobromomethane	BQL	20	μg/L		
1,2-Dichloroethane	BQL	. 10	μg/L	<b>A</b>	
Ethylbenzene	BQL	10	μ <b>g/L</b>		
Monochlorobenzene	BQL ,	50	μg/L	•	
Tetrachloroethylene	BQL ~	10	μg/L		*
Toluene	BQL	10	μg/L		
Trichloroethylene	BQL	10	μg/L	•	
Vinyl chloride	BQL	10	μg/L		

## Attachment G

## Wasteload and Limit Calculations

- Mixing Zone Calculations (MIXER)
- Antidegradation Wasteload Allocation Spreadsheet
- STATS Program Results

## Mixing Zone Predictions for

## Pembroke WWTP

Effluent Flow = 0.20 MGD Stream 7Q10 = 486 MGD Stream 30Q10 = 600 MGD Stream 1Q10 = 407 MGD Stream slope = 0.0013 ft/ft Stream width = 750 ft Bottom scale = 4 Channel scale = 1

Mixing Zone Predictions @ 7Q10

Depth = 1.7837 ft Length = 259720.68 ft Velocity = .5626 ft/sec Residence Time = 5.3431 days

#### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than 37.43% of the 7Q10 is used.

## Mixing Zone Predictions @ 30Q10

Depth = 2.0245 ft Length = 233609.89 ft Velocity = .6119 ft/sec Residence Time = 4.4187 days

#### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than 45.26% of the 30Q10 is used.

## Mixing Zone Predictions @ 1Q10

Depth = 1.6033 ft Length = 283939.31 ft Velocity = .5242 ft/sec

Residence Time = 150.4667 hours

### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than .66% of the 1Q10 is used.

## FRESHWATER WATER QUALITY CRITERIA / WASTELOAD ALLOCATION ANALYSIS

Facility Name:

Pembroke WWTP

Permit No.: VA0088048

Receiving Stream:

**New River** 

Version: OWP Guidance Memo 00-2011 (8/24/00)

Mean Hardness (as CaCO3) =	67.8	mg/L
90% Temperature (Annual) =	24.2	deg C
90% Temperature (Wet season) =	17	deg C
90% Maximum pH =	8.3	SU
10% Maximum pH =	7.1	SU
Tier Designation (1 or 2) =	2	
Public Water Supply (PWS) Y/N? =	n	
Trout Present Y/N? =	n	
Early Life Stages Present Y/N? =	у	

1Q10 (Annual) =	407	MGD
7Q10 (Annual) =	486	MGD
30Q10 (Annual) =	600	MGD
1Q10 (Wet season) =	600	MGD
30Q10 (Wet season)	1087	MGD
30Q5 =	708	MGD
Harmonic Mean =	1605	MGD

Mixing Information													
Annual - 1Q10 Mix =	0.66	%											
- 7Q10 Mix =	37.43	%											
- 30Q10 Mix =	45.26	%											
Wet Season - 1Q10 Mix =	100	%											
- 30Q10 Mix =	100	%											

Effluent Information		
Mean Hardness (as CaCO3) =	53.8	mg/L
90% Temp (Annual) =	22.5	deg C
90% Temp (Wet season) =	16.6	deg C
90% Maximum pH =	7.9	SU
10% Maximum pH =	6.2	SU
Discharge Flow =	0.2	MGD

Parameter	Background Conc.		Water Qua	ality Criteria			Wasteload All		,	Antidegrada	ation Baseline	9	. AI	ntidegradatio	on Allocation	s	Most Limiting Allocations				
(ug/l unless noted)		Acute	Chronic	HH (PWS)	НН	Acute	Chronic HH	(PWS)	НН	Acute	Chronic	HH (PWS)	нн	Acute	Chronic.	HH (PWS)	НН	Acute	Chronic	HH (PWS)	нн
Acenapthene	0	**		na	9.9E+02	-	-	na	3.5E+06	-		na	9.9E+01	-	-	na	3.5E+05		-	na	3.5E+05
Acrolein	0	-	-	na	9.3E+00		-	na	3.3E+04	-	-	na	9.3E-01	-	-	na	3.3E+03	-	-	na	3.3E+03
Acrylonitrile <sup>C</sup>	0	-	-	na	2.5E+00	-	-	na	2.0E+04	-		na	2.5E-01	_	-	na	2.0E+03	-	_	na	2.0E+03
Aldrin <sup>C</sup> Ammonia-N (mg/l)	0	3.0E+00	-	na	5.0E-04	4.3E+01	-	na	4.0E+00	7.5E-01	-	na	5.0E-05	1.5E+03	-	na	4.0E-01	4.3E+01	-	na	4.0E-01
(Yearly) Ammonia-N (mg/l)	0	5.13E+00	8.17E-01	na	-	7.4E+01	1.1E+03	na	-	1.18E+00	2.04E-01	na		2.4E+03	6.1E+02	na	-	7.4E+01	6.1E+02	na	-
(High Flow)	0	4.72E+00	1.30E+00	na	-	1.4E+04	7.1E+03	na	-	1.18E+00	3.25E-01	na	-	3.5E+03	1.8E+03	na		3.5E+03	1.8E+03	na	-
Anthracene	0	-	-	na	4.0E+04	-	-	na	1.4E+08	-		na	4.0E+03	-	-	na	1.4E+07	-	-	na	1.4E+07
Antimony	0	-	- 1	na	6.4E+02	-	-	na	2.3E+06	-	-	na	6.4E+01	-	-	na	2.3E+05	-	-	na	2.3E+05
Arsenic	0	3.4E+02	1.5E+02	na	-	4.9E+03	1.4E+05	na	-	8.5E+01	3.8E+01	na		1.7E+05	9.1E+04	na	-	4.9E+03	9.1E+04	na	-
Barium	0	-	-	na	-	-	-	na	-	-		na		-	-	na	-	-		na	-
Benzene <sup>C</sup>	0	-	-	na	5.1E+02		-	na	4.1E+06	-	-	na	5.1E+01	-	-	na	4.1E+05			na	4.1E+05
Benzidine <sup>C</sup>	0	-	-	na	2.0E-03		-	na	1.6E+01	-		na	2.0E-04	-	-	na	1.6E+00	-		na	1.6E+00
Benzo (a) anthracene <sup>C</sup>	0	-	-	na	1.8E-01	-	-	na	1.4E+03	-		na	1.8E-02	-	-	na	1.4E+02	-		na	1.4E+02
Benzo (b) fluoranthene <sup>C</sup>	0	-	-	na	1.8E-01	-	1	na	1.4E+03	-	-	na	1.8E-02	-	-	na	1.4E+02	-	-	na	1.4E+02
Benzo (k) fluoranthene <sup>C</sup>	0	-	-	na	1.8E-01	-	-	na	1.4E+03	-		na	1.8E-02	-	-	na	1.4E+02	-		na	1.4E+02
Benzo (a) pyrene <sup>c</sup>	0	-	-	na	1.8E-01	-	-	na	1.4E+03	-	-	na	1.8E-02	-	-	na	1.4E+02		-	na	1.4E+02
Bis2-Chloroethyl Ether C	0	-	-	na	5.3E+00	-	-	na	4.3E+04	-	_	na	5.3E-01	-	_	na	4.3E+03		-	na	4.3E+03
Bis2-Chloroisopropyl Ether	0	-	-	na	6.5E+04			na	2.3E+08	-	-	na	6.5E+03	-	_	na	2.3E+07	-	-	na	2.3E+07
Bis 2-Ethylhexyl Phthalate <sup>C</sup>	0	-	-	na	2.2E+01	-		na	1.8E+05	-		na	2.2E+00	_	-	na	1.8E+04			na	1.8E+04
Bromoform <sup>C</sup>	0	-	-	na	1.4E+03	-	_	na	1.1E+07	_	-	na	1.4E+02	-	_	na	1.1E+06			na	1.1E+06
Butylbenzylphthalate	0	-	-	na	1.9E+03	-	-	na	6.7E+06	-	_	na	1.9E+02	_	_	na	6.7E+05			na	6.7E+05
Cadmium	0	2.5E+00	8.4E-01	na	-	3.6E+01	7.6E+02	na	-	6.3E-01	2.1E-01	na	-	1.3E+03	5.1E+02	na	-	3.6E+01	5.1E+02	na	-
Carbon Tetrachloride <sup>C</sup>	0		-	na	1.6E+01	-	-	na	1.3E+05		-	na	1.6E+00		_	na	1.3E+04			na	1.3E+04
Chlordane <sup>C</sup>	0	2.4E+00	4.3E-03	na	8.1E-03	3.5E+01	3.9E+00	na	6.5E+01	6.0E-01	1.1E-03	na	8.1E-04	1.2E+03	2.6E+00	na	6.5E+00	3.5E+01	2.6E+00	na	6.5E+00
Chloride	0	8.6E+05	2.3E+05	na	-	1.2E+07	2.1E+08	na	-	2.2E+05	5.8E+04	na	-	4.4E+08	1.4E+08	na	-	1.2E+07	1.4E+08	na	
TRC	0	1.9E+01	1.1E+01	na		2.7E+02	1.0E+04	na	_	4.8E+00	2.8E+00	na	_	9.7E+03	6.7E+03	na	-	2.7E+02	6.7E+03	na	
Chlorobenzene	0	-	_	na	1.6E+03	-	-	na	5.7E+06	-		na	1.6E+02	-	-	na	5.7E+05		0.72+03	na	5.7E+05

Parameter	Background		Water Qua	lity Criteria			Wasteload	Allocations			Antidegrada	tion Baseline	9	A	ntidegradatio	on Allocation	s	Most Limiting Allocations			
(ug/l unless noted)	Conc.	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	нн
Chlorodibromomethane <sup>C</sup>	0		_	na	1.3E+02			na	1.0E+06	-		na	1.3E+01			na	1.0E+05			na	1.0E+05
Chloroform	0	_	_	na	1.1E+04	-	_	na	3.9E+07	_	_	na	1.1E+03	-	_	na	3.9E+06			na	3.9E+06
2-Chloronaphthalene	0	_	-	na	1.6E+03	_		na	5.7E+06		_	na	1.6E+02	-		na	5.7E+05	-		na	5.7E+05
2-Chlorophenol	0	_	_	na	1.5E+02			na	5.3E+05			na	1.5E+01			na	5.3E+04	-		na	5.3E+04
Chlorpyrifos	0	8.3E-02	4.1E-02	na	-	1.2E+00	3.7E+01	na	-	2.1E-02	1.0E-02	na	-	4.2E+01	2.5E+01	na	J.JL104	1.2E+00	2.5E+01		
Chromium III	0	4.1E+02	5.4E+01	na	_	5.9E+03	4.9E+04	na		1.0E+02	1.3E+01	na		2.1E+05	3.3E+04	na	_	5.9E+03	3.3E+04	na	-
Chromium VI	0	1.6E+01	1.1E+01	na	-	2.3E+02	1.0E+04			4.0E+00	2.8E+00			8.1E+03	6.7E+03		_		6.7E+03	na	
Chromium, Total	0	-	1.12.01	1.0E+02	_	2.52.102	1.02104	na na		4.02.700	2.02+00	na 1.0E+01		0. IE+03		na 3.5E+04		2.3E+02		na	-
Chrysene C	0			na	1.8E-02			na	1.4E+02				1.8E-03		-		4 45.04			na	-
	1.61	9.2E+00	6.4E+00		1.05-02	1.1E+02	4.4E+03			3.5E+00	2 85+00	na		2.05.02	205.02	na	1.4E+01	445.00		na	1.4E+01
Copper Cyanide, Free		2.2E+01		na				na	F 7F . 07		2.8E+00	na	4.05.00	3.9E+03	2.9E+03	na	-	1.1E+02	2.9E+03	na	
DDD C	0	2.25	5.2E+00	na	1.6E+04	3.2E+02	4.7E+03	na	5.7E+07	5.5E+00	1.3E+00	na	1.6E+03	1.1E+04	3.2E+03	na	5.7E+06	3.2E+02	3.2E+03	na	5.7E+06
DDE C	0		-	na	3.1E-03		-	na	2.5E+01	-	-	na	3.1E-04	-	-	na	2.5E+00	-		na	2.5E+00
DDT <sup>c</sup>	0			na	2.2E-03	-		na	1.8E+01	-		na	2.2E-04	-	-	na	1.8E+00	-	-	na	1.8E+00
	0	1.1E+00	1.0E-03	na	2.2E-03	1.6E+01	9.1E-01	na	1.8E+01	2.8E-01	2.5E-04	na	2.2E-04	5.6E+02	6.1E-01	na	1.8E+00	1.6E+01	6.1E-01	na	1.8E+00
Demeton	0	-	1.0E-01	na	-	-	9.1E+01	na	-	-	2.5E-02	na	-	-	6.1E+01	na		-	6.1E+01	na	-
Diazinon	0	1.7E-01	1.7E-01	na	-	2.5E+00	1.5E+02	na	-	4.3E-02	4.3E-02	na	-	8.7E+01	1.0E+02	na	-	2.5E+00	1.0E+02	na	
Dibenz(a,h)anthracene c	0	-	-	na	1.8E-01	-	-	na	1.4E+03		-	na	1.8E-02	-	-	na	1.4E+02	-	-	na	1.4E+02
1,2-Dichlorobenzene	0	-	-	na	1.3E+03	-	-	na	4.6E+06	-	-	na	1.3E+02	-	-	na	4.6E+05	-	-	na	4.6E+05
1,3-Dichlorobenzene	0	-	- 8	na	9.6E+02	-	-	na	3.4E+06	-	-	na	9.6E+01	-	-	na	3.4E+05	-	-	na	3.4E+05
1,4-Dichlorobenzene	0	-	-	na	1.9E+02	-	-	na	6.7E+05	-	-	na	1.9E+01	-	-	na	6.7E+04	-	-	na	6.7E+04
3,3-Dichlorobenzidine <sup>C</sup>	0	-	-	na	2.8E-01	-	-	na	2.2E+03	-	-	na	2.8E-02	-	-	na	2.2E+02	-	-	na	2.2E+02
Dichlorobromomethane <sup>C</sup>	0	-	-	na	1.7E+02	-	-	na	1.4E+06	-	-	na	1.7E+01	-	-	na	1.4E+05	-	-	na	1.4E+05
1,2-Dichloroethane <sup>C</sup>	0	-	-	na	3.7E+02	-	-	na	3.0E+06	-	-	na	3.7E+01	-	-	na	3.0E+05		-	na	3.0E+05
1,1-Dichloroethylene	0	-	-	na	7.1E+03	-	-	na	2.5E+07	-	-	na	7.1E+02	-	-	na	2.5E+06		-	na	2.5E+06
1,2-trans-dichloroethylene	0	-	-	na	1.0E+04	-	-	na	3.5E+07	-	-	na	1.0E+03	-	-	na	3.5E+06	-	-	na	3.5E+06
2,4-Dichlorophenol	0	-	-	na	2.9E+02	-	-	na	1.0E+06	-	-	na	2.9E+01	-	-	na	1.0E+05	-	-	na	1.0E+05
2,4-Dichlorophenoxy	0	_	_	na				na				na	_			na	_	_		200	
acetic acid (2,4-D) 1,2-Dichloropropane <sup>c</sup>	0			na	1.5E+02			na	1.2E+06				1.5E+01						-	na	4.05+05
1,3-Dichloropropene <sup>C</sup>	0	_		na	2.1E+02				1.7E+06	_		na				na	1.2E+05	-	-	na	1.2E+05
Dieldrin <sup>C</sup>	0		5.6E-02		5.4E-04			na	A service and the service and		4 45 00	na	2.1E+01	4.05.00	0.45.04	na	1.7E+05			na	1.7E+05
Diethyl Phthalate	0	2.4E-01	3.0E-02	na		3.5E+00	5.1E+01	na	4.3E+00	6.0E-02	1.4E-02	na .	5.4E-05	1.2E+02	3.4E+01	na	4.3E-01	3.5E+00	3.4E+01	na	4.3E-01
2,4-Dimethylphenol			-	na	4.4E+04			na	1.6E+08			na	4.4E+03	-	- 5	na	1.6E+07	-		na	1.6E+07
	0	-	_	na	8.5E+02	-		na	3.0E+06	-		na	8.5E+01	-	-	na	3.0E+05	-		na	3.0E+05
Dimethyl Phthalate	0		-	na	1.1E+06	-		na	3.9E+09	-	-	na	1.1E+05		-	na	3.9E+08	-	-	na	3.9E+08
Di-n-Butyl Phthalate	0	-	-	na	4.5E+03			na	1.6E+07	Sin in	100	na	4.5E+02	-	-	na	1.6E+06	-	-	na	1.6E+06
2,4 Dinitrophenol	0	-	-	na	5.3E+03	-	-	na	1.9E+07	-		na	5.3E+02	-	-	na	1.9E+06	-	-	na	1.9E+06
2-Methyl-4,6-Dinitrophenol	0	-	-	na	2.8E+02	-	-	na	9.9E+05	-	-	na	2.8E+01	-	-	na	9.9E+04	-	-	na	9.9E+04
2,4-Dinitrotoluene <sup>c</sup> Dioxin 2,3,7,8-	0	-	-	na	3.4E+01	-	-	na	2.7E+05	-	-	na	3.4E+00	-	-	na	2.7E+04	-	-	na	2.7E+04
tetrachlorodibenzo-p-dioxin	0		-	na	5.1E-08	-	-	na	1.8E-04	-	-	na	5.1E-09	-	_	na	1.8E-05	-		na	1.8E-05
1,2-Diphenylhydrazine <sup>C</sup>	0	-	-	na	2.0E+00	-	-	na	1.6E+04	-	-	na	2.0E-01	-	-	na	1.6E+03	-	_	na	1.6E+03
Alpha-Endosulfan	0	2.2E-01	5.6E-02	na	8.9E+01	3.2E+00	5.1E+01	na	3.2E+05	5.5E-02	1.4E-02	na	8.9E+00	1.1E+02	3.4E+01	na	3.2E+04	3.2E+00	3.4E+01	na	3.2E+04
Beta-Endosulfan	0	2.2E-01	5.6E-02	na	8.9E+01		5.1E+01	na	3.2E+05	5.5E-02	1.4E-02	na	8.9E+00	1.1E+02	3.4E+01	na	3.2E+04	3.2E+00	3.4E+01	na	3.2E+04
Alpha + Beta Endosulfan	0	2.2E-01	5.6E-02	_	-	100 m 300	5.1E+01		-	5.5E-02	1.4E-02	-	-	1.1E+02	3.4E+01	-	-	3.2E+00	3.4E+01		5.22.04
Endosulfan Sulfate	0			na	8.9E+01		-	na	3.2E+05	5.02.02		na	8.9E+00		5.42101	na	3.2E+04	3.22+00		na	3.2E+04
Endrin	0	8.6E-02	3.6E-02	na	6.0E-02	1.2E+00		na	2.1E+02	2.2E-02	9.0E-03	na	6.0E-03	4.4E+01	2.2E+01	na	2.1E+01	1.2E+00	2.2E+01		2.1E+01
Endrin Aldehyde	0	0.0L-02	5.02-02	na	3.0E-01		J.JE+01	na	1.1E+03	2.2E-02	9.0E-03	na	3.0E-02	4.46+01	2.25+01	na	1.1E+02	1.22+00	2.2E+01	na na	1.1E+02

Parameter	Background		Water Quality Criteria				Wasteload	Allocations	S		Antidegradat	tion Baseline	9	A	ntidegradation	Allocation	S	Most Limiting Allocations			
(ug/l unless noted)	Conc.	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic H	H (PWS)	нн	Acute	Chronic	HH (PWS)	нн
Ethylbenzene	0	-	-	na	2.1E+03	_	_	na	7.4E+06	_		na	2.1E+02	_	-	na	7.4E+05	-	-	na	7.4E+05
Fluoranthene	0		_	na	1.4E+02	_	_	na	5.0E+05		-	na	1.4E+01	_	_	na	5.0E+04	-	-	na	5.0E+04
	0			na	5.3E+03			na	1.9E+07			na	5.3E+02			na	1.9E+06			na	1.9E+06
Fluorene																					
Foaming Agents	0			na	-	-		na	-			na	-		0.45.00	na	-	-	0.45.00	na	
Guthion	0	-	1.0E-02	na	-	-	9.1E+00	na	-	-	2.5E-03	na		-	6.1E+00	na	-		6.1E+00	na	-
Heptachlor <sup>c</sup>	0	5.2E-01	3.8E-03	na	7.9E-04	7.5E+00	3.5E+00	na	6.3E+00	1.3E-01	9.5E-04	na	7.9E-05	2.6E+02	2.3E+00	na	6.3E-01	7.5E+00	2.3E+00	na	6.3E-01
Heptachlor Epoxide <sup>C</sup>	0	5.2E-01	3.8E-03	na	3.9E-04	7.5E+00	3.5E+00	na	3.1E+00	1.3E-01	9.5E-04	na	3.9E-05	2.6E+02	2.3E+00	na	3.1E-01	7.5E+00	2.3E+00	na	3.1E-01
Hexachlorobenzene	0	-	-	na	2.9E-03	-	-	na	2.3E+01		-	na	2.9E-04	-	-	na	2.3E+00	**	-	na	2.3E+00
Hexachlorobutadiene <sup>c</sup>	0	-		na	1.8E+02	-	-	na	1.4E+06	-		na	1.8E+01	-	-	na	1.4E+05	-	-	na	1.4E+05
Hexachlorocyclohexane																					
Alpha-BHC <sup>C</sup>	0	-	-	na	4.9E-02	-	-	na	3.9E+02	-	-	na	4.9E-03	-	-	na	3.9E+01	-	-	na	3.9E+01
Hexachlorocyclohexane Beta-BHC <sup>C</sup>					4.75.04				4 45 402				1 7E 00				4 45+02				4.45+02
Hexachlorocyclohexane	0		-	na	1.7E-01	-		na	1.4E+03			na	1.7E-02			na	1.4E+02			na	1.4E+02
Gamma-BHC <sup>C</sup> (Lindane)	0	9.5E-01	na	na	1.8E+00	1.4E+01	-	na	1.4E+04	2.4E-01	-	na	1.8E-01	4.8E+02		na	1.4E+03	1.4E+01		na	1.4E+03
Hexachlorocyclopentadiene	0			na	1.1E+03		_	na	3.9E+06		-	na	1.1E+02	_	_	na	3.9E+05		_	na	3.9E+05
Hexachloroethane <sup>C</sup>	0			na	3.3E+01		_		2.6E+05				3.3E+00			na	2.6E+04		-		2.6E+04
						-		na				na			4.05.00					na	
Hydrogen Sulfide	0		2.0E+00	na	-	-	1.8E+03	na	-	-	5.0E-01	na		-	1.2E+03	na	-	-	1.2E+03	na	
Indeno (1,2,3-cd) pyrene <sup>C</sup>	0	-	-	na	1.8E-01	-	-	na	1.4E+03	-	-	na	1.8E-02	-	-	na	1.4E+02	-	-	na	1.4E+02
Iron	0	-	-	na	-	-	-	na	-	-	-	na	-	-	-	na	-		-	na	
Isophorone	0	-	-	na	9.6E+03	-	-	na	7.7E+07	-	-	na	9.6E+02	-	-	na	7.7E+06	-	-	na	7.7E+06
Kepone	0	-	0.0E+00	na	-	-	0.0E+00	na	-	-	0.0E+00	na	-	-	0.0E+00	na	-	-	0.0E+00	na	-
Lead	0	7.1E+01	8.2E+00	na	-	1.0E+03	7.5E+03	na	-	1.8E+01	2.1E+00	na	-	3.7E+04	5.0E+03	na	-	1.0E+03	5.0E+03	na	-
Malathion	0		1.0E-01	na	-	-	9.1E+01	na	-	-	2.5E-02	na		-	6.1E+01	na	-	-	6.1E+01	na	-
Manganese	78.9	-	-	na	-	-	-	na	-	-	-	na	-	-	-	na	-	-		na	-
Mercury	0	1.4E+00	7.7E-01			2.0E+01	7.0E+02			3.5E-01	1.9E-01		-	7.1E+02	4.7E+02		-	2.0E+01	4.7E+02		
Methyl Bromide	0			na	1.5E+03	_	-	na	5.3E+06	-	-	na	1.5E+02	_	_	na	5.3E+05	_		na	5.3E+05
Methylene Chloride C	0		_	na	5.9E+03	_	_	na	4.7E+07	-	-	na	5.9E+02	_	_	na	4.7E+06	_	-	na	4.7E+06
Methoxychlor	0		3.0E-02	na	-		2.7E+01	na	-	_	7.5E-03	na	-	_	1.8E+01	na	-	_	1.8E+01	na	-
	0						0.0E+00							_					0.0E+00		
Mirex		4.05.00	0.0E+00	na		105.00		na	4.05.07	0.05.04	0.0E+00	na	4.05.00		0.0E+00	na	4.05.00	405.00		na	4.05.00
Nickel	0	1.3E+02	1.5E+01	na	4.6E+03	1.9E+03	1.3E+04	na	1.6E+07	3.3E+01	3.6E+00	na	4.6E+02	6.7E+04	8.9E+03	na	1.6E+06	1.9E+03	8.9E+03	na	1.6E+06
Nitrate (as N)	. 0	-	-	na	-	-	-	na		-	-	na	-	-	-	na	-	-	-	na	-
Nitrobenzene	0	-	-	na	6.9E+02	-	-	na	2.4E+06	-	-	na	6.9E+01	-	-	na	2.4E+05	-	-	na	2.4E+05
N-Nitrosodimethylamine <sup>c</sup>	0	-	-	na	3.0E+01	-	-	na	2.4E+05	-	-	na	3.0E+00	-	-	na	2.4E+04	-	-	na	2.4E+04
N-Nitrosodiphenylamine <sup>c</sup>	0	-	-	na	6.0E+01	-	-	na	4.8E+05	-	-	na	6.0E+00	-	-	na	4.8E+04	-	-	na	4.8E+04
N-Nitrosodi-n-propylamine <sup>C</sup>	0		-	na	5.1E+00	-	-	na	4.1E+04	-	-	na	5.1E-01	-	-	na	4.1E+03	-	-	na	4.1E+03
Nonylphenol	0	2.8E+01	6.6E+00	-	-	4.0E+02	6.0E+03	na	-	7.0E+00	1.7E+00	-	-	1.4E+04	4.0E+03	-	-	4.0E+02	4.0E+03	na	-
Parathion	0	6.5E-02	1.3E-02	na	-	9.4E-01	1.2E+01	na	-	1.6E-02	3.3E-03	na	-	3.3E+01	7.9E+00	na	-	9.4E-01	7.9E+00	na	-
PCB Total <sup>C</sup>	0	-	1.4E-02	na	6.4E-04	-	1.3E+01	na	5.1E+00	-	3.5E-03	na	6.4E-05		8.5E+00	na	5.1E-01	-	8.5E+00	na	5.1E-01
Pentachlorophenol <sup>C</sup>	0	8.1E+00	7.4E+00	na	3.0E+01	1.2E+02	6.7E+03	na	2.4E+05	2.4E+00	1.8E+00	na	3.0E+00	4.9E+03	4.5E+03	na	2.4E+04	1.2E+02	4.5E+03	na	2.4E+04
Phenol	0	_		na	8.6E+05		-	na	3.0E+09		_	na	8.6E+04		_	na	3.0E+08			na	3.0E+08
Pyrene	0			na	4.0E+03			na	1.4E+07			na	4.0E+02			na	1.4E+06			na	1.4E+06
Radionuclides																					
Gross Alpha Activity	0		-	na	-	-		na				na	-	-		na		-		na	
(pCi/L)	0	-	-	na	-	-	-	na	-	-	-	na	-	-	-	na	-	-		na	-
Beta and Photon Activity					105.55																4.45.00
(mrem/yr)	0	-	-	na	4.0E+00	-	-	na	1.4E+04	-	-	na	4.0E-01	-	-	na	1.4E+03	-	-	na	1.4E+03
Radium 226 + 228 (pCi/L)	0	-	-	na	-	-	-	na	-	-	-	na	-	-	-	na	-	-	-	na	-
Uranium (ug/l)	0	-	-	na	-		-	na	-	-	-	na	-	-	-	na				na	-

Parameter	Background		Water Qual	lity Criteria			Wasteload	Allocations			Antidegrada	tion Baseline		Ar	ntidegradati	on Allocations	S		Most Limit	ing Allocation	ıs
(ug/l unless noted)	Conc.	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН	Acute	Chronic	HH (PWS)	НН
Selenium, Total Recoverable	0	2.0E+01	5.0E+00	na	4.2E+03	2.9E+02	4.6E+03	na	1.5E+07	5.0E+00	1.3E+00	na	4.2E+02	1.0E+04	3.0E+03	na	1.5E+06	2.9E+02	3.0E+03	na	1.5E+06
Silver	0	1.7E+00	-	na	-	2.5E+01	-	na	-	4.4E-01	-	na	-	9.0E+02	-	na	-	2.5E+01		na	-
Sulfate	0	-	-	na		-	-	na	-	-		na	-	-	-	na	-		-	na	-
1,1,2,2-Tetrachloroethane <sup>C</sup>	0	-	-	na	4.0E+01	-	-	na	3.2E+05	-	-	na	4.0E+00	-	_	na	3.2E+04	-	-	na	3.2E+04
Tetrachloroethylene <sup>C</sup>	0	-	-	na	3.3E+01	-	-	na	2.6E+05	-	-	na	3.3E+00			na	2.6E+04			na	2.6E+04
Thallium	0	-	-	na	4.7E-01	-		na	1.7E+03	-	-	na	4.7E-02	-	-	na	1.7E+02	-	-	na	1.7E+02
Toluene	0	-	-	na	6.0E+03	-	-	na	2.1E+07	-	-	na	6.0E+02	-	-	na	2.1E+06	-	-	na	2.1E+06
Total dissolved solids	0	-	-	na	-	-	-	na	-	-	-	na	-		-	na	-			na	-
Toxaphene <sup>C</sup>	0	7.3E-01	2.0E-04	na	2.8E-03	1.1E+01	1.8E-01	na	2.2E+01	1.8E-01	5.0E-05	na	2.8E-04	3.7E+02	1.2E-01	na	2.2E+00	1.1E+01	1.2E-01	na	2.2E+00
Tributyltin	0	4.6E-01	7.2E-02	na		6.6E+00	6.6E+01	na	-	1.2E-01	1.8E-02	na	-	2.3E+02	4.4E+01	na	-	6.6E+00	4.4E+01	na	-
1,2,4-Trichlorobenzene	0	-	-	na	7.0E+01	-	-	na	2.5E+05	-	-	na	7.0E+00		-	na	2.5E+04		-	na	2.5E+04
1,1,2-Trichloroethane <sup>C</sup>	0	-	-	na	1.6E+02	-	-	na	1.3E+06	-	-	na	1.6E+01	-	-	na	1.3E+05	-	-	na	1.3E+05
Trichloroethylene <sup>C</sup>	0		-	na	3.0E+02	-	-	na	2.4E+06	-	-	na	3.0E+01	-	-	na	2.4E+05	-	-	na	2.4E+05
2,4,6-Trichlorophenol <sup>C</sup>	0	-	-	na	2.4E+01	-	-	na	1.9E+05	-	-	na	2.4E+00	-	-	na	1.9E+04		-	na	1.9E+04
2-(2,4,5-Trichlorophenoxy) propionic acid (Silvex)	0	-	-	na	-	-	-	na	-	-	-	na	-	-	-	na	-		-	na	-
Vinyl Chloride <sup>C</sup>	0	-	-	na	2.4E+01	-	-	na	1.9E+05	-	-	na	2.4E+00		-	na	1.9E+04	-	-	na	1.9E+04
Zinc	7.26	8.3E+01	8.5E+01	na	2.6E+04	1.1E+03	7.1E+04	na	9.2E+07	2.7E+01	2.7E+01	na	2.6E+03	3.9E+04	4.7E+04	na	9.2E+06	1.1E+03	4.7E+04	na	9.2E+06

#### Notes:

- 1. All concentrations expressed as micrograms/liter (ug/l), unless noted otherwise
- 2. Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals
- 3. Metals measured as Dissolved, unless specified otherwise
- 4. "C" indicates a carcinogenic parameter
- Regular WLAs are mass balances (minus background concentration) using the % of stream flow entered above under Mixing Information. Antidegradation WLAs are based upon a complete mix.
- 6. Antideg. Baseline = (0.25(WQC background conc.) + background conc.) for acute and chronic
  - = (0.1(WQC background conc.) + background conc.) for human health
- 7. WLAs established at the following stream flows: 1Q10 for Acute, 30Q10 for Chronic Ammonia, 7Q10 for Other Chronic, 30Q5 for Non-carcinogens and Harmonic Mean for Carcinogens. To apply mixing ratios from a model set the stream flow equal to (mixing ratio 1), effluent flow equal to 1 and 100% mix.

Metal	Target Value (SSTV)
Antimony	2.3E+05
Arsenic	2.0E+03
Barium	na
Cadmium	1.4E+01
Chromium III	2.4E+03
Chromium VI	9.2E+01
Copper	4.4E+01
Iron	na
Lead	4.1E+02
Manganese	na
Mercury	8.1E+00
Nickel	7.5E+02
Selenium	1.2E+02
Silver	1.0E+01
Zinc	4.4E+02

Note: do not use QL's lower than the minimum QL's provided in agency guidance

·	0.200 MGD DISCHAR	GE FLOW - STREAM MIX PER '	'Mix.exe"		
Discharge Flow Used for WQS-WLA Calculation	ons (MGE 0.200	Ammonia - Dry Season - Acu	ite	Ammonia - Dry Season - Chro	nic_
Stream Flows Allocated to Mix (MGD) Stre. Dry Season Wet Season Dry 1Q10 2.686 600.000 2 7Q10 181.910 N/A 18 30Q10 271.560 1087.000 27 30Q5 708.000 N/A 70 Harm Mean 1605.000 N/A 160	Total Mix Flows  sam + Discharge (MGD)  Season Wet Season  2.886 600.200  32.110 N/A  71.760 1087.200  08.200 N/A  05.200 N/A  0.200 N/A	90th Percentile pH (SU) (7.204 - pH) (pH - 7.204)  Trout Present Criterion (mg N/I Trout Absent Criterion (mg N/L Trout Present?  Effective Criterion (mg N/L)	8.257 -1.053 1.053 3.426 5.129 n 5.129	90th Percentile Temp. (deg C) 90th Percentile pH (SU) MIN MAX (7.688 - pH) (pH - 7.688)  Early LS Present Criterion (mg N Early LS Absent Criterion (mg N) Early Life Stages Present?  Effective Criterion (mg N/L)	24.199 8.300 1.527 24.199 -0.612 0.612 0.817 0.817 y 0.817
Dry	<u>Season</u> <u>Wet Season</u> 4.082 17.000	Ammonia - Wet Season - Acc	ute	Ammonia - Wet Season - Chro	nic
30Q10 90th% Temp. Mix (deg C) 24 1Q10 90th% pH Mix (SU) 8 30Q10 90th% pH Mix (SU) 8 1Q10 10th% pH Mix (SU) 6 7Q10 10th% pH Mix (SU) 7	4.092 17.000 4.199 17.000 3.257 8.300 3.300 8.300 5.929 N/A 7.097 N/A  culated Formula Inputs 66.8 66.8 67.8 67.8	90th Percentile pH (SU) (7.204 - pH) (pH - 7.204)  Trout Present Criterion (mg N/I Trout Absent Criterion (mg N/L Trout Present? Effective Criterion (mg N/L)	8.300 -1.096 1.096 3.150 4.717 n 4.717	90th Percentile Temp. (deg C) 90th Percentile pH (SU) MIN MAX (7.688 - pH) (pH - 7.688)  Early LS Present Criterion (mg N Early LS Absent Criterion (mg N) Early Life Stages Present? Effective Criterion (mg N/L)	17.000 8.300 2.429 17.000 -0.612 0.612 1.299 1.299 y 1.299

			0.200	MGD DISCHAF	RGE FLOW - COMPLETE STREA	M MIX		
Discharge Flo	w Used for W	OS-WLA Calc	culations (MGI	0.200	Ammonia - Dry Season - Ac	ute	Ammonia - Dry Season - Chro	nic
1Q10 7Q10 30Q10 30Q5 Harm. Mean Annual Avg.	100% Str. Allocated to Dry Season 407.000 486.000 600.000 708.000 1605.000 0.000	eam Flows o Mix (MGD) Wet Season 600.000 N/A 1087.000 N/A N/A N/A	Total N Stream + Dis Dry Season 407.200 486.200 600.200 708.200 1605.200 0.200	/lix Flows scharge (MGD)	90th Percentile pH (SU) (7.204 - pH) (pH - 7.204)  Trout Present Criterion (mg N/I Trout Absent Criterion (mg N/I Trout Present? Effective Criterion (mg N/L)	8.300 -1.096 1.096 3.151 4.718 n 4.718	90th Percentile Temp. (deg C) 90th Percentile pH (SU) MIN MAX (7.688 - pH) (pH - 7.688)  Early LS Present Criterion (mg N Early LS Absent Criterion (mg N) Early Life Stages Present? Effective Criterion (mg N/L)	24.199 8.300 1.527 24.199 -0.612 0.612 0.817 0.817 9
4040 00450/ 3		m/Discharge N	Dry Season	Wet Season	Ammonia - Wet Season - Ac	ute	Ammonia - Wet Season - Chro	nic
1Q10 90th% 7 30Q10 90th% 1 Q10 90th% 1 30Q10 90th% 1 Q10 10th% 1 7Q10 10th% 1 1Q10 Hardne:	Temp. Mix (doth Mix (SU)  pH Mix (SU)  strict (SU)	leg C)	24.199 24.199 8.300 8.300 7.099 7.099 Calculated 67.793 67.794	17.000 17.000 8.300 8.300 N/A N/A Formula Inputs 67.793 67.794	90th Percentile pH (SU) (7.204 - pH) (pH - 7.204)  Trout Present Criterion (mg N/I Trout Absent Criterion (mg N/L Trout Present? Effective Criterion (mg N/L)	8.300 -1.096 1.096 3.150 4.717 n 4.717	90th Percentile Temp. (deg C) 90th Percentile pH (SU) MIN MAX (7.688 - pH) (pH - 7.688)  Early LS Present Criterion (mg N Early LS Absent Criterion (mg N) Early Life Stages Present? Effective Criterion (mg N/L)	17.000 8.300 2.429 17.000 -0.612 0.612 1.299 1.299 1.299

#### 6/20/2013 9:35:55 AM

```
Facility = Pembroke WWTP
Chemical = hydrogen sulfide (mg/L)
Chronic averaging period = 4
WLAa =
WLAc = 1200
Q.L. = 1.0
# samples/mo. = 1
# samples/wk. = 1
```

#### **Summary of Statistics:**

```
# observations = 1

Expected Value = 1.4

Variance = .7056

C.V. = 0.6

97th percentile daily values = 3.40678

97th percentile 4 day average = 2.32930

97th percentile 30 day average = 1.68847

# < Q.L. = 0

Model used = BPJ Assumptions, type 2 data
```

No Limit is required for this material

The data are:

1.4

#### 6/20/2013 9:33:29 AM

```
Facility = Pembroke WWTP
Chemical = total copper (ug/L)
Chronic averaging period = 4
WLAa = 110
WLAc = 2900
Q.L. = 10
# samples/mo. = 1
# samples/wk. = 1
```

#### Summary of Statistics:

```
# observations = 1
Expected Value = 12
Variance = 51.84
C.V. = 0.6
97th percentile daily values = 29.2010
97th percentile 4 day average = 19.9654
97th percentile 30 day average = 14.4726
# < Q.L. = 0
Model used = BPJ Assumptions, type 2 data
```

No Limit is required for this material

The data are:

#### 6/20/2013 9:37:37 AM

```
Facility = Pembroke WWTP
Chemical = total zinc (ug/L)
Chronic averaging period = 4
WLAa = 1100
WLAc = 47000
Q.L. = 50
# samples/mo. = 1
# samples/wk. = 1
```

#### Summary of Statistics:

```
# observations = 1
Expected Value = 89
Variance = 2851.56
C.V. = 0.6
97th percentile daily values = 216.574
97th percentile 4 day average = 148.077
97th percentile 30 day average = 107.338
# < Q.L. = 0
Model used = BPJ Assumptions, type 2 data
```

No Limit is required for this material

The data are:

#### 3/19/2013 2:19:01 PM

Facility = Pembroke WWTP
Chemical = TRC (ug/L)
Chronic averaging period = 4
WLAa = 270
WLAc = 6700
Q.L. = 0.2
# samples/mo. = 90
# samples/wk. = 23

#### Summary of Statistics:

# observations = 1
Expected Value = 1000
Variance = 360000
C.V. = 0.6
97th percentile daily values = 2433.41
97th percentile 4 day average = 1663.79
97th percentile 30 day average = 1206.05
# < Q.L. = 0
Model used = BPJ Assumptions, type 2 data

A limit is needed based on Acute Toxicity

Maximum Daily Limit = 270

Average Weekly limit = 139.181114805761

Average Monthly Llmit = 124.154821746445

Only 124 mg 14

The data are:

#### 3/19/2013 2:17:13 PM

```
Facility = Pembroke WWTP
Chemical = ammonia (mg/L)
Chronic averaging period = 30
WLAa = 74
WLAc = 610
Q.L. = 0.2
# samples/mo. = 1
# samples/wk. = 1
```

#### Summary of Statistics:

```
# observations = 1
Expected Value = 9
Variance = 29.16
C.V. = 0.6
97th percentile daily values = 21.9007
97th percentile 4 day average = 14.9741
97th percentile 30 day average = 10.8544
# < Q.L. = 0
Model used = BPJ Assumptions, type 2 data
```

No Limit is required for this material

The data are:

## Attachment H

**Reduced Monitoring Evaluation Memorandum** 

#### MEMORANDUM

## DEPARTMENT OF ENVIRONMENTAL QUALITY Blue Ridge Regional Office

#### 3019 Peters Creek Road

Roanoke, VA 24019

SUBJECT:

Justification for Reduced Monitoring Frequency

Reissuance of VPDES Permit No. VA0088048

Pembroke WWTP

TO:

Permit File

FROM:

Becky L. France, Water Permit Writer Blo

DATE:

May 22, 2013

#### **Compliance History**

The VPDES Permit Manual recommends effluent monitoring frequencies. Guidance Memo 98-2005 allows for reduced monitoring at facilities with excellent compliance histories. To qualify for consideration of reduced monitoring, the facility should not have been issued any Letter of Noncompliance (LON), Notice of Violation (NOV), Warning Letter, or Notice of Unsatisfactory Laboratory Evaluations, or be under any Consent Orders, Consent Decrees, Executive Compliance Agreements, or related enforcement documents during the past three years.

The facility has not received any warning letters or NOVs. A DEQ compliance inspection conducted on December 13, 2011 identified some deficiencies related to clerical errors, calculation errors, needed updates to the Operations and Maintenance Manual, requested testing documentation, and flow meter out of paper. According to a letter dated February 21, 2012, Pembroke WWTP took steps to address all of these deficiencies. A DEQ compliance inspection conducted on April 26, 2013 identified a need for increased maintenance and operations controls for solids removal and disinfection redundancy. In a letter dated April 30, 2013, the permittee noted completion of the requested operational controls. There are no outstanding compliance or enforcement issues at this treatment facility. Therefore, the permittee qualifies for a reduced monitoring data evaluation.

#### Monitoring Data Evaluation

Discharge Monitoring Report (DMR) data from May 2010 through April 2013 were reviewed and tabulated in the attached tables. Total suspended solids (TSS), pH, and biochemical oxygen demand (BOD<sub>5</sub>) have been considered for reduced monitoring. Total residual chlorine limits are not considered eligible for reduced monitoring to ensure protection of aquatic life and human health. The actual performance to permit limit ratios are summarized in the table that follows. Facilities with baseline monitoring that have an actual performance to permit limit ratio of greater than 75 percent are not eligible for reduced monitoring.

Justification Memorandum for Reduced Monitoring VPDES Permit No. VA0088048
Page 2 of 5

Table 1 Performance to Permit Limit Ratios (DMR Data)

Parameter	Actual Performance/ Permit Limit Monthly Average*	Actual Performance/ Permit Limit (Maximum)*	Reduced Monitoring
TSS	11%, 5.8%	13%, 6.4%	1/Week
BOD <sub>5</sub>	20%, 11%	23%, 12%	1/Week
pН	5		1/Day

<sup>\*</sup>The ratio based upon concentration is listed first, and the ratio based upon loading is listed second.

pH: Several of the reported values were within 0.5 S.U. of the limit. So, the pH monitoring frequency has been continued at 1/day.

TSS and BOD<sub>5</sub>: The DMR data are consistently well below the permit limits. According to Guidance Memo 98-2005, facilities with 3 days/week baseline monitoring that have an actual performance to permit limit ratio of less than 25 percent are eligible for a reduced monitoring frequency of 1/week. The monitoring frequency for BOD<sub>5</sub> and TSS has been reduced from 3 days/week to 1/week.

The permit will contain a special condition that will revert the TSS and BOD<sub>5</sub> monitoring frequencies back to 3 days/week if a Notice of Violation is issued for any of the parameters with reduced monitoring. The permittee is still expected to take all appropriate measures to control both the average and maximum concentrations of the pollutants of concern, regardless of any reductions in monitoring frequencies.

Justification Memorandum for Reduced Monitoring (VA0088048)
Page 3 of 5

Table 2 Flow DMR Data for Pembroke WWTP

		I
Date DMR	MGD	
Due	Monthly Ave.	MGD Max.
10-Jun-10	0.099	0.144
10-Jul-10	0.084	0.125
10-Aug-10	0.089	0.112
10-Sep-10	0:096	0.135
10-Oct-10	0.11	0.16
10-Nov-10	0.12	0.147
10-Dec-10	0.096	0.204
10-Jan-11	0.116	0.221
10-Feb-11	0.119	0.138
10-Маг-11	0.123	0.165
10-Apr-11	0.117	0.291
10-May-11	0.107	0.154
10-Jun-11	111	0.185
10-Jul-11	0.087	0.122
10-Aug-11	0.085	0.116
10-Sep-11	0.087	0.098
10-Oct-11	0.092	0.135
10-Nov-11	0.096	0.106
10-Dec-11	0.091	0.121
10-Jan-12	0.098	0.171
10-Feb-12	0.092	0.11
10-Mar-12	0.095	0.141
10-Apr-12	0.088	0.121
10-May-12	0.09	0.118
10-Jun-12	0.093	0.12
10-Jul-12	0.087	0.107
10-Aug-12	0.087	0.132
10-Sep-12	0.089	0.107
10-Oct-12	0.093	0.169
10-Nov-12	0.086	0.101
10-Dec-12	0.084	0.1
10-Jan-13	0.088	0.104
10-Feb-13	0.092	0.214
10-Mar-13	0.092	0.114
10-Apr-13	0.087	0.100
10-May-13	0.089	0.124

Table 3 TSS and BOD<sub>5</sub> DMR Data for Pembroke WWTP

	TSS BOD <sub>5</sub>							
Due Date	average	max	average	max	average	max	average	max
	kg/d	kg/d	mg/L	mg/L	kg/d	kg/d	mg/L	mg/L
10-Jun-10		1.9	4.1	6.3	2.7	5.2	6.3	11
10-Jul-10		2.7	5.3	8.3	1.5	1.9	4.7	6
10-Aug-10		1.1	2.9	3.7	0.9	1.3	2.8	3
10-Sep-10		9.5	8.7	19.2	3.9	8.5	9.6	18
10-Oct-10		6.4	8	14.7	5.4	6.9	12.9	16
10-Nov-10		1.6	2.6	3.7	3.4	6.6	7.6	15
10-Dec-10		2	4.6	4.7	4.3	5.5	9.6	13
10-Jan-11	1.7	2.1	4.2	6	2.9	4.1	6.8	9
10-Feb-11	1.8	2.7	4.2	6	5.2	9.8	11.6	22
10-Mar-11	1.4	2.8	3.2	6.3	2.5	3.2	5.3	7
10-Apr-11	1.9	2.8	4.9	8.3	4	9.5	10.6	27
10-May-11	1.8	3	4.7	8	4.7	10	12.3	27
10-Jun-11	1.1	1.5	2.5	4.3	4.2	6.1	10.4	14
10-Jul-11	0.7	8.0	2	2.7	1.9	2	5.8	6
10-Aug-11	0.5	0.6	1.5	2	0.9	1.3	2.7	4
10-Sep-11	0.6	0.7	1.9	2.3	1.3	1.3	4.1	4
10-Oct-11	0.8	1	2.3	3	1.6	2.6	4.5	7
10-Nov-11	0.6	0.7	1.5	2	0.1	0.6	0.4	2
10-Dec-11	0.5	0.7	1.5	2	0.5	0.5	1.4	4
10-Jan-12	0.8	1	2.2	3	3.3	4.2	6.3	9.
10-Feb-12	0.8	1	2.4	3	. 1.9	2	2.6	5
10-Mar-12	0.7	1.2	2.1	3.3	2.3	4.1	6.8	13
10-Apr-12	0.7	8.0	2.1	2.3	1.3	2.4	4.2	7
10-May-12		0.6	1.5	1.7	1.4	3	4.1	8
10-Jun-12		1.4	2.2	4	1.3	2.1	3.8	6
10-Jul-12	0.6	0.7	1.7	2	0.6	0.9	1.5	3
10-Aug-12		1	2.3	3.3	0.4	1	0.9	2
10-Sep-12		0.9	1.5	2.7	0.4	1.1	1.2	3
10-Oct-12		0.8	1.7	2.3	0.2	0.7	0.5	2
10-Nov-12	1.2	1.5	3.6	4.3	0.3	1	1.3	3
10-Dec-12		1.8	3.7	5.3	2.2	3	6.8	9
10-Jan-13		2.6	2.9	7.7	1.6	3.6	4.8	11
10-Feb-13		11.7	10	24.7	4.3	15.1	. 9.4	27
10-Mar-13		1.9	3.1	5.3	3.9	7	11.2	20
10-Apr-13		3.6	5.2	10.7	2.7	5.6	8.2	16
10-May-13	1.2	1.3	3.5	4.0	2.9	3.0	8.6	9.0
mean	1.27	2.18	3.40	5.6	2.30	4.08	5.88	10.22
maximum	4.00	11.70	10.00	24.70	5.40	15.10	12.90	27.00
minimum	0.5	0.6	1.5	1.7	0.1	0.5	0.4	2
permit limit	22	34	30	45	22	34	30	45
performance /	_	_					'	ŀ
permit fimit)	5.8	6.4	11	13	10.5	12.0	20	23
100								

#### Justification Memorandum for Reduced Monitoring (VA0088048) Page 5 of 5

Table 4 pH DMR Data for Pembroke WWTP

Date DMR			Γ	<u> </u>
Due	pH, min S.U.	H ion conc	pH, max S.U.	H ion conc
10-Jun-10	6.28	5.248E-07	7.83	1.479E-08
10-Jul-10	7.28	5.248E-08	7.72	1.905E-08
10-Aug-10	7.23	5.888E-08	7.73	1.862E-08
10-Sep-10	7.25	5.623E-08	7.87	1.349E-08
10-Oct-10	7.42	3.802E-08	7.84	1.445E-08
10-Nov-10	7.17	6.761E-08	7.95	1.122E-08
10-Dec-10	6.75	1.778E-07	7.53	2.951E-08
10-Jan-11	6.24	5.754E-07	7.35	4.467E-08
10-Feb-11	6.46	3.467E-07	7.11	7.762E-08
10-Mar-11	6.35	4.467E-07	7.29	5.129E-08
10-Apr-11	6.49	3.236E-07	7.13	7.413E-08
10-May-11	6.56	2.754E-07	7.48	3.311E-08
10-Jun-11	7.29	5.129E-08	7.8	1.585E-08
10-Jul-11	7.53	2.951E-08	8.18	6.607E-09
10-Aug-11	7.34	4.571E-08	7.98	1.047E-08
10-Sep-11	7.33	4.677E-08	7.9	1.259E-08
10-Oct-11	7.35	4.467E-08	7.77	1.698E-08
10-Nov-11	6.36	4.365E-07	7.74	1.820E-08
10-Dec-11	6.39	4.074E-07	7.39	4.074E-08
10-Jan-12	6.04	9.120E-07	7.1	7.943E-08
10-Feb-12	6.3	5.012E-07	7.53	2.951E-08
10-Mar-12	6.02	9.550E-07	6.73	1.862E-07
10-Apr-12	6.22	6.026E-07	6.82	1.514E-07
10-May-12	6.18	6.607E-07	7.08	8.318E-08
10-Jun-12	6.37	4.266E-07	7.07	8.511E-08
10-Jul-12	6.46	3.467E-07	7.36	4.365E-08
10-Aug-12	6.47	3.388E-07	7.19	6.457E-08
10-Sep-12	6.5	3.162E-07	7.2	6.310E-08
10-Oct-12	6.19	6.457E-07	7.23	5.888E-08
10-Nov-12	6.33	4.677E-07	7.02	9.550E-08
10-Dec-12	6.17	6.761E-07	6.63	2.344E-07
10-Jan-13	6.06	8.710E-07	6.79	1.622E-07
10-Feb-13	6.17	6.761E-07	7.72	1.905E-08
10-Mar-13	6.61	2.455E-07	7.56	2.754E-08
10-Apr-13	7.08	8.318E-08	7.58	2.630E-08
10-May-13	6.58	2.630E-07	7.76	1.738E-08

pH min. pH max 6.02 S.U.

8.18 S.U.

## **Attachment I**

**Regional Water Quality Model (Version 4.0)** 

```
modout.txt
"Model Run For C:\Users\pmp94864\Documents\Working
files\BECKY\PERMITS\VPDES\Pembroke WWTP\Reissuance 2013\Data\Pembroke Model 2013.mod
On 7/3/2013 12:03:59 PM"
"Model is for NEW RIVER."
"Model starts at the PEMBROKE WWTP discharge."
"Background Data" "7Q10", "CBOD5",
"7Q10", "cBOD5", "TKN", "DO", "(mgd)", "(mg/1)", "(mg/1)", "(mg/1)", "(mg/1)", 485.846, 2, 0, 7.154,
                                                                  "Temp"
                                                                 "deg C"
                                0,
"Discharge/Tributary Input Data for Segment 1"
"Flow", "CBOD5", "TKN", "DO", "Temp"
"(mgd)", "(mg/1)", "(mg/1)", "(deg C"
.2, 30, 20, ,0, 22.5
"Hydraulic Information for Segment 1"
"Length", "Width", "Depth", "Velocity"
"(mi)", "(ft)", "(ft)", "(ft/sec)"
.60606, 749.999, 2.1, .505
                                                 "(ft/sec)"
"Initial Mix Values for Segment 1"
"Flow", "DO", "CBOD", "nBOD",
"(mgd)", "(mg/l)", "(mg/l)", "(mg/l)",
486.046, 7.151, 5.029, .03,
                                                                  "DOSat".
                                                                                "Temp"
                                                                 "(mg/l)"
                                                                              ", "deg C"
                                                                  7.95,
"Rate Constants for Segment 1. - (All units Per Day)" "k1", "k1@T", "k2", "k2@T", "kn", "kn@T", "BD", .5, .606, 3.96, 4.375, .25, .345, 0,
                                                                                             "BD@T"
"Output for Segment 1"
"Segment starts at PEMBROKE WWTP"
"Total", "Segm."
"Dist.", "Dist.",
"(mi)", "(mi)",
                                "DO",
"(mg/1)",
                                                 "cBOD"
                                                                  "nBOD"
                                                "(mg/1)"
                                                                 "(mg/1)"
                                                 5.029,
٥,
               0,
.1,
                                7.151,
                                                                  .03
.1,
                                7.155,
                                                                  .03
2,
                                7.155,
               .2,
                                                                  .03
                                7.155,
3,
               .3,
                                                                  .03
.4,
.5,
               .4,
                                7.155,
                                                                  .03
               . 5
                                7.155,
                                                                  .03
.606,
               .606,
                                7.155.
                                                                  .03
```

<sup>&</sup>quot;END OF FILE"

#### REGIONAL MODELING SYSTEM **VERSION 4.0** Model Input File for the Discharge to NEW RIVER.

#### File Information

File Name:

C:\Users\pmp94864\Documents\Working files\BECKY\PERMITS\VPDES\P

Date Modified:

July 03, 2013

#### Water Quality Standards Information

Stream Name:

**NEW RIVER New River Basin** 

River Basin: Section:

Class:

IV - Mountainous Zones Waters

Special Standards:

#### **Background Flow Information**

Gauge Used:

**Eggleston Gauge** 

Gauge Drainage Area:

2961 Sq.Mi. 474 MGD

Gauge 7Q10 Flow:

3035 Sq.Mi.

Headwater Drainage Area: Headwater 7Q10 Flow:

485.846 MGD (Net; includes Withdrawals/Discharges)

Withdrawal/Discharges:

0 MGD

Incremental Flow in Segments:

0.1600811 MGD/Sq.Mi.

#### **Background Water Quality**

Background Temperature:

24.2 Degrees C

Background cBOD5: Background TKN:

2 mg/l

0 mg/l

Background D.O.:

7.154099 mg/l

#### **Model Segmentation**

Number of Segments:

Model Start Elevation:

1680 ft above MSL

Model End Elevation:

1676 ft above MSL

# REGIONAL MODELING SYSTEM VERSION 4.0 Model Input File for the Discharge to NEW RIVER.

A discharge enters.

#### **Segment Information for Segment 1**

**Definition Information** 

Segment Definition: Discharge Name:

PEMBROKE WWTP

VPDES Permit No.: VA0088048

Discharger Flow Information

 Flow:
 0.2 MGD

 cBOD5:
 30 mg/l

 TKN:
 20 mg/l

 D.O.:
 0 mg/l

Temperature: 22.5 Degrees C

Geographic Information

Segment Length: 0.60606 miles
Upstream Drainage Area: 3035 Sq.Mi.
Downstream Drainage Area: 0 Sq.Mi.
Upstream Elevation: 1680 Ft.
Downstream Elevation: 1676 Ft.

Hydraulic Information

Segment Width: 749.999 Ft.
Segment Depth: 2.1 Ft.
Segment Velocity: 0.505 Ft./Sec.
Segment Flow: 486.046 MGD

Incremental Flow: -513.917 MGD (Applied at end of segment.)

Channel Information

Cross Section: Rectangular

Character: Moderately Meandering

Pool and Riffle: No

Bottom Type: Large Rock Sludge: None Plants: None Algae: None

# REGIONAL MODELING SYSTEM VERSION 4.0 Model Input File for the Discharge to NEW RIVER.

#### **Segment Information for Segment 1**

**Definition Information** 

Segment Definition: A discharge enters.

Discharge Name: PEMBROKE WWTP

VPDES Permit No.: VA0088048

**Discharger Flow Information** 

 Flow:
 0.2 MGD

 cBOD5:
 30 mg/l

 TKN:
 20 mg/l

 D.O.:
 0 mg/l

Temperature: 22.5 Degrees C

Geographic Information

Segment Length: 0.60606 miles
Upstream Drainage Area: 3035 Sq.Mi.
Downstream Drainage Area: 0 Sq.Mi.
Upstream Elevation: 1680 Ft.
Downstream Elevation: 1676 Ft.

Hydraulic Information

Segment Width: 749.999 Ft.
Segment Depth: 2.1 Ft.
Segment Velocity: 0.505 Ft /Sec.

Segment Velocity: 0.505 Ft./Sec. Segment Flow: 514.117 MGD

Incremental Flow: -513.917 MGD (Applied at end of segment.)

Channel Information

Cross Section: Rectangular

Character: Moderately Meandering

Pool and Riffle: No

Bottom Type: Large Rock

Sludge: None Plants: None Algae: None

Attachment J

**Public Notice** 

#### PUBLIC NOTICE - Environmental Permit

PURPOSE OF NOTICE: To seek public comment on a draft permit from the Department of Environmental Quality that will allow the release of treated wastewater into a water body in Giles County, Virginia

PUBLIC COMMENT PERIOD: August 1, 2013 through August 30, 2013

PERMIT NAME: Virginia Pollutant Discharge Elimination System Permit – Wastewater issued by DEQ, under the authority of the State Water Control Board

APPLICANT NAME, ADDRESS, AND PERMIT NUMBER: Town of Pembroke, PO Box 5, Pembroke, VA 24136, VA0088048

FACILITY NAME AND LOCATION: Pembroke WWTP, 126 Park Lane, Pembroke, VA 24136

PROJECT DESCRIPTION: Pembroke WWTP has applied for a reissuance of a permit for the public wastewater treatment plant. The applicant proposes to release treated sewage wastewater at a rate of 200,000 gallons per day from the current facility into a water body. Sludge from the treatment process will be periodically transported to the New River Resource Authority for disposal. The facility proposes to release the treated sewage into the New River in the New River Watershed (VAW-N29R). A watershed is the land area drained by a river and its incoming streams. The permit will limit the following pollutants to amounts that protect water quality: organic matter, solids, toxic pollutants HOW TO COMMENT AND/OR REQUEST A PUBLIC HEARING: DEQ accepts comments and requests for public hearing by e-mail, fax, or postal mail. All comments and requests must be in writing and be received by DEO during the comment period. Submittals must include the names, mailing addresses and telephone numbers of the commenter/requester and of all persons represented by the commenter/requester. A request for a public hearing must also include: 1) The reason why a public hearing is requested. 2) A brief, informal statement regarding the nature and extent of the interest of the requester or of those represented by the requestor, including how and extent such interest would be directly and adversely affected by the permit. 3) Specific references, where possible, to terms and conditions of the permit with suggested revisions. A public hearing may be held, including another comment period, if a public response is significant, based on individual requests for a public hearing, and there are substantial, disputed issues relevant to the permit.

CONTACT FOR PUBLIC COMMENTS, DOCUMENT REQUESTS, AND ADDITIONAL INFORMATION: Becky L. France; ADDRESS: Virginia Department of Environmental Quality, Blue Ridge Regional Office, 3019 Peters Creek Road, Roanoke, VA 24019-2738; (540) 562-6700; E-MAIL ADDRESS: becky.france@deq.virginia.gov; FAX: (540) 562-6725. The public may review the draft permit and application at the DEQ office named above by appointment or may request copies of the documents from the contact person listed above.

Attachment K

**EPA Checksheet** 

treatment process?

## State "FY2003 Transmittal Checklist" to Assist in Targeting Municipal and Industrial Individual NPDES Draft Permits for Review

#### Part I. State Draft Permit Submission Checklist

In accordance with the MOA established between the Commonwealth of Virginia and the United States Environmental Protection Agency, Region III, the Commonwealth submits the following draft National Pollutant Discharge Elimination System (NPDES) permit for Agency review and concurrence.

Facility Name:	Pembroke WWTP			
NPDES Permit Number:	VA0088048			
Permit Writer Name:	Becky L. France			
Date:	3/19/13			
Major [ ]	Minor [X] Industrial [ ]	Muni	icipal []	X]
I.A. Draft Permit Package S	Submittal Includes:	Yes	No	N/A
1. Permit Application?		Х		
Complete Draft Permit (tincluding boilerplate info	for renewal or first time permit – entire permit, rmation)?	x		
3. Copy of Public Notice?		X		
4. Complete Fact Sheet?	,	X		
5. A Priority Pollutant Scree	ening to determine parameters of concern?	X		
6. A Reasonable Potential	analysis showing calculated WQBELs?	X		
7. Dissolved Oxygen calcu	lations?	X		
8. Whole Effluent Toxicity	Test summary and analysis?			X
9. Permit Rating Sheet for	new or modified industrial facilities?			X
I.B. Permit/Facility Charac	eteristics	Yes	No	N/A
1. Is this a new, or currently	y unpermitted facility?		X	
•	lls (including combined sewer overflow points, non- water) from the facility properly identified and	X		
3. Does the fact sheet <b>or</b> p	ermit contain a description of the wastewater	-		

I.B. Permit/Facility Characteristics – cont. (FY2003)	Yes	No	N/A
<ol> <li>Does the review of PCS/DMR data for at least the last 3 years indicate significant non-compliance with the existing permit? under consent order</li> </ol>	х		
5. Has there been any change in streamflow characteristics since the last permit was developed?	х		
6. Does the permit allow the discharge of new or increased loadings of any pollutants?		x	
7. Does the fact sheet or permit provide a description of the receiving water body(s) to which the facility discharges, including information on low/critical flow conditions and designated/existing uses?	X		
8. Does the facility discharge to a 303(d) listed water?	X	,	
a. Has a TMDL been developed and approved by EPA for the impaired water?		Х	
b. Does the record indicate that the TMDL development is on the State priority list and will most likely be developed within the life of the permit?	X		
c. Does the facility discharge a pollutant of concern identified in the TMDL or 303(d) listed water?		X	
<ol> <li>Have any limits been removed, or are any limits less stringent, than those in the current permit</li> </ol>		х	
10. Does the permit authorize discharges of storm water?			X
11. Has the facility substantially enlarged or altered its operation or substantially increased its flow or production?		X	
12. Are there any production-based, technology-based effluent limits in the permit?		X	
13. Do any water quality-based effluent limit calculations differ from the State's standard policies or procedures?		X	
14. Are any WQBELs based on an interpretation of narrative criteria?		X	
15. Does the permit incorporate any variances or other exceptions to the State's standards or regulations?		X	
16. Does the permit contain a compliance schedule for any limit or condition?		X	
17. Is there a potential impact to endangered/threatened species or their habitat by the facility's discharge(s)?		X	
18. Have impacts from the discharge(s) at downstream potable water supplies been evaluated?			х
19. Is there any indication that there is significant public interest in the permit action proposed for this facility?		X	
20. Have previous permit, application, and fact sheet been examined?	X		

### Part II. NPDES Draft Permit Checklist (FY2003)

# Region III NPDES Permit Quality Checklist – for POTWs (To be completed and included in the record <u>only</u> for POTWs)

II.A. Permit Cover Page/Administration	Yes	No	N/A
Does the fact sheet or permit describe the physical location of the facility, including latitude and longitude (not necessarily on permit cover page)?	X		
Does the permit contain specific authorization-to-discharge information (from where to where, by whom)?	X		

11.1	B. Effluent Limits – General Elements	Yes	No	N/A
1.	Does the fact sheet describe the basis of final limits in the permit (e.g., that a comparison of technology and water quality-based limits was performed, and the most stringent limit selected)?	X		
2.	Does the fact sheet discuss whether "antibacksliding" provisions were met for any limits that are less stringent than those in the previous NPDES permit?			x

II.C. Technology-Based Effluent Limits (POTWs)		Yes	No	N/A
1.	Does the permit contain numeric limits for <u>ALL</u> of the following: BOD (or alternative, e.g., CBOD, COD, TOC), TSS, and pH?	X		Section 1
2.	Does the permit require at least 85% removal for BOD (or BOD alternative) and TSS (or 65% for equivalent to secondary) consistent with 40 CFR Part 133?	X		
	a. If no, does the record indicate that application of WQBELs, or some other means, results in more stringent requirements than 85% removal or that an exception consistent with 40 CFR 133.103 has been approved?			X
3.	Are technology-based permit limits expressed in the appropriate units of measure (e.g., concentration, mass, SU)?	X		
4.	Are permit limits for BOD and TSS expressed in terms of both long term (e.g., average monthly) and short term (e.g., average weekly) limits?	X		
5.	Are any concentration limitations in the permit less stringent than the secondary treatment requirements (30 mg/l BOD5 and TSS for a 30-day average and 45 mg/l BOD5 and TSS for a 7-day average)?		X	
	a. If yes, does the record provide a justification (e.g., waste stabilization pond, trickling filter, etc.) for the alternate limitations?			<b>X</b> ,

II.D. Water Quality-Based Effluent Limits		Yes	No	N/A
1.	Does the permit include appropriate limitations consistent with 40 CFR 122.44(d) covering State narrative and numeric criteria for water quality?	X		
2.	Does the fact sheet indicate that any WQBELs were derived from a completed and EPA approved TMDL?			х

II.D. Water Quality-Based Effluent Limits – cont. (FY2003)			No	N/A
3.	3. Does the fact sheet provide effluent characteristics for each outfall?			
4.	Does the fact sheet document that a "reasonable potential" evaluation was performed?	X		
	a. If yes, does the fact sheet indicate that the "reasonable potential" evaluation was performed in accordance with the State's approved procedures?	X		
	b. Does the fact sheet describe the basis for allowing or disallowing in-stream dilution or a mixing zone?	X		
	c. Does the fact sheet present WLA calculation procedures for all pollutants that were found to have "reasonable potential"?	X		
	d. Does the fact sheet indicate that the "reasonable potential" and WLA calculations accounted for contributions from upstream sources (i.e., do calculations include ambient/background concentrations)?			X
	e. Does the permit contain numeric effluent limits for all pollutants for which "reasonable potential" was determined?	X		
5.	Are all final WQBELs in the permit consistent with the justification and/or documentation provided in the fact sheet?	X		
6.	For all final WQBELs, are BOTH long-term AND short-term effluent limits established?	X		
7.	Are WQBELs expressed in the permit using appropriate units of measure (e.g., mass, concentration)?	X		
8.	Does the record indicate that an "antidegradation" review was performed in accordance with the State's approved antidegradation policy?	X	,	

II.E. Monitoring and Reporting Requirements		Yes	No	N/A
1.	Does the permit require at least annual monitoring for all limited parameters and other monitoring as required by State and Federal regulations?	X		
	a. If no, does the fact sheet indicate that the facility applied for and was granted a monitoring waiver, AND, does the permit specifically incorporate this waiver?			X
2.	Does the permit identify the physical location where monitoring is to be performed for each outfall?	X		
3.	Does the permit require at least annual influent monitoring for BOD (or BOD alternative) and TSS to assess compliance with applicable percent removal requirements?		X	
4.	Does the permit require testing for Whole Effluent Toxicity?		X	

II.F. Special Conditions		Yes	No	N/A
1.	Does the permit include appropriate biosolids use/disposal requirements?	Х		
2.	Does the permit include appropriate storm water program requirements?			X

II.F. Special Conditions – cont. (FY2003)			No	N/A
3.	If the permit contains compliance schedule(s), are they consistent with statutory and regulatory deadlines and requirements?			X
4.	Are other special conditions (e.g., ambient sampling, mixing studies, TIE/TRE, BMPs, special studies) consistent with CWA and NPDES regulations?	X		
5.	Does the permit allow/authorize discharge of sanitary sewage from points other than the POTW outfall(s) or CSO outfalls [i.e., Sanitary Sewer Overflows (SSOs) or treatment plant bypasses]?		. <b>X</b>	
6.	Does the permit authorize discharges from Combined Sewer Overflows (CSOs)?			X
	a. Does the permit require implementation of the "Nine Minimum Controls"?			X
	b. Does the permit require development and implementation of a "Long Term Control Plan"?			X
	c. Does the permit require monitoring and reporting for CSO events?			X
7.	Does the permit include appropriate/ Pretreatment Program requirements?			X

II.G. Standard Conditions			Yes	No	N/A
Does the <b>permit</b> contain all 40 CFR 122.41 standard conditions or the State equivalent (or more stringent) conditions?			X		
List of Standard Conditions – 4	0 CFR 122.41				
Duty to comply Duty to reapply Need to halt or reduce activity not a defense Duty to mitigate Proper O & M Permit actions	Property rights Duty to provide information Inspections and entry Monitoring and records Signatory requirement Bypass Upset	Reporting R Planned Anticipal Transfer Monitori Complia 24-Hour Other no	change ted nond s ng repor nce sche reportin	complial ts edules g	nce
equivalent or more stringent c	dditional standard condition (or the onditions) for POTWs regarding nand new industrial users [40 CFR	otification of	X		

Part II.	NPDES Draft Permit Checklist (FY2003),
	Region III NPDES Permit Quality Review Checklist – For Non-Municipals
	(To be completed and included in the record for <u>all</u> non-POTWs)
	NOT APPLICABLE

### Part III. Signature Page (FY2003)

Based on a review of the data and other information submitted by the permit applicant, and the draft permit and other administrative records generated by the Department/Division and/or made available to the Department/Division, the information provided on this checklist is accurate and complete, to the best of my knowledge.

Name	Becky L. France
Title	Water Permit Writer
Signature	Beeky Drance
Date	3/19/13